

STATE OF OREGON
WATER SUPPLY WELL REPORT

MARI 72302

WELL I.D. LABEL# L

156297

START CARD #

1083159

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

9/27/2026

(1) LAND OWNER

Owner Well I.D. _____

First Name _____ Last Name _____

Company SINN FARMS INC

Address 9510 SARATOGA DR NE

City SILVERTON State OR Zip 97381

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
 Material From To Amt sacks/lbs
 Seal: _____

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger

☐ Reverse Rotary ☐ Other _____

(4) PROPOSED USE

☐ Domestic ☒ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering

☐ Thermal ☐ Injection ☐ Other _____

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 564.00 ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amt	sacks/lbs
14	0	195	Bentonite	0	6	4	S
12	195	364	Calculated			4	
8	364	564	Cement	6	364	380.5	S
			Calculated			176	

Seal placement method: ☐ A ☐ B ☒ C ☐ D ☐ E ☒ Other: POURED & PROBED

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from _____ ft. to _____ ft. Material _____ Size _____

Explosives used: ☐ Type _____ Amount _____

Seal Placement Begin Date 8/24/2026 Begin Time 17 15

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount _____ Actual Amount _____

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	8	☒	1.5	364	0.250	ST	☒		OUT.	364

Temp casing ☒ Yes Dia 12 From + ☒ 1 To 195

(7) PERFORATIONS/SCREENS

Perforations Method _____

Screens Type _____ Material _____

Perf/ Screen	Casing/ Liner	Screen Dia	From	To	Scrn/slot width	Slot length	# of slots	Tele/ Pipe size

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	375		564	4

Temperature 59 °F Lab analysis ☐ Yes By _____

Water quality concerns? ☐ Yes (describe below) TDS amount 312 ppm

From	To	Description	Amount	Units

(9) LOCATION OF WELL (legal description)

County MARION Twp 6.00 S N/S Range 1.00 W E/W WM

Sec 28 NW 1/4 of the NE 1/4 Tax Lot 1000

Tax Map Number _____ Lot _____

Lat _____ " or 45.02489000 DMS or DD

Long _____ " or -122.81483000 DMS or DD

☐ Street address of well ☒ Nearest address

DIRECTLY NORTH OF 6638 OLD MT. ANGEL HWY, SILVERTON, OR 97381

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	8/28/2026			102.71
Flowing Artesian?		☐	Dry Hole?	
		☐		

WATER BEARING ZONES

Depth water was first found 31.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
8/12/2026	31	48	5			23.33
8/13/2026	72	120	10			50.17
8/14/2026	168	174	20			94
8/18/2026	275	280	60			57.25
8/28/2026	365	564	375			102.71

(11) WELL LOG

Ground Elevation 192.87 FT

Material	From	To
Soil	0	1
Clay Brown	1	4
Clay Grey Sticky	4	7
Clay Brown	7	10
Clay Grey	10	25
Clay Grey with Gravel	25	31
Large Gravel Grey	31	48
Sand & Gravel Brown	48	53
Silt Grey	53	60
Clay Grey with some Gravel	60	72
Gravel	72	120
Clay with Gravel	120	125
Packed Silt Grey	125	137
Clay Grey Medium	137	155
Clay Blue	155	160
Silt Grey	160	168
Cemented Sand with Pea Gravel	168	174
Clay Blue	174	178
Clay Grey	178	205

Construction

Begin Date 8/12/2026 Begin Time 14 00 End Date 8/28/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number 1358 Date 9/27/2026

Signed BYRON STADELI (E-filed)

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1487 Date 9/27/2026

Signed DANIEL STADELI (E-filed)

Drilling Company: Westerberg Drilling, Inc.

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MARI 72302

9/27/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.02489000 Datum: WGS84

Longitude: -122.81483000

Township/Range/Section/Quarter-Quarter Section:
WM6.00S1.00W28NWNE

Address of Well:

DIRECTLY NORTH OF 6638 OLD MT. ANGEL HWY, SILVERTON, OR 97581

Well Label: 156297

Printed: September 1, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

