

WATER WELL REPORT

WATER RESOURCES DEPARTMENT.

SALEM, OREGON 97310

within 30 days from the date
of well completion.

STATE OF OREGON

(Please type or print)

Do not write above this line)

State Well No.

State Permit No.

(1) OWNER:

Name Gene & Susan Richardson
Address 5382 Sunnyview Rd N.E.
Salem, OR.

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Jetted ☐
D. ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(10) LOCATION OF WELL:

County MARION Driller's well number

NE 1/4 NE 1/4 Section 20 T. 7S R. 2W W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 46 ft.

Static level 7 ft. below land surface. Date 1-9-80

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 8

Depth drilled 150 ft. Depth of completed well 150 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsoil, Clayey	0	3	
Clay, yellow	3	36	
Clay, gray	36	46	
Gravel coarse,			
loosely cemented	46	61	
Clay, gray	61	72	
Gravel coarse,			
cemented	72	148	

RECEIVED

SEP 08 1980

WATER RESOURCES DEPT
SALEM, OREGON

(5) CASING INSTALLED:

Threaded ☐ Welded ☒

8 " Diam. from 1 ft. to 147 ft. Gage 250
" Diam. from " ft. to " ft. Gage
" Diam. from " ft. to " ft. Gage

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Mills Knife

Size of perforations 3/16 in. by 3 in.
300 perforations from 40 ft. to 141 ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from " ft. to " ft.

Diam. Slot size Set from " ft. to " ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☐ Yes ☒ No If yes, by whom?

Yield: gal./min. with " ft. drawdown after " hrs.

" " " " "

" " " " "

Water test 160 gal./min. with 3 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered " ft.

(9) CONSTRUCTION:

Well seal—Material used Cement

Well sealed from land surface to 20 ft.

Diameter of well bore to bottom of seal 12 in.

Diameter of well bore below seal 8 in.

Number of sacks of cement used in well seal 16 sacks

How was cement grout placed?
Gravity flow

Was a drive shoe used? ☒ Yes ☐ No Plugs " Size: location " ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: "

Gravel placed from " ft. to " ft.

Work started 11-28 1979 Completed 1-9- 1980

Date well drilling machine moved off of well 1-9- 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Gene F. Richardson Date 8-15, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 738

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name Richardson Well Drilling
(Person, firm or corporation) (Type or print)

Address 5382 Sunnyview Rd NE
Salem

[Signed] Gene F. Richardson
(Water Well Contractor)

Contractor's License No. 650 Date 8-15-, 1980