

NOTICE TO WATER WELL CONTRACTOR  
The original and first copy of this report  
are to be filed with the

**RECEIVED**

**WATER WELL REPORT**

WATER RESOURCES DEPARTMENT  
SALEM, OREGON 97310  
within 30 days from  
of well completion.

DEC 5 1978

STATE OF OREGON  
(Please type or print)

WATER RESOURCES DEPT.  
SALEM, OREGON

(Do not write above this line)

MAR 17 1979

45/11W-23da

State Well No. ....  
State Permit No. ....

**(1) OWNER:**

Name Leonard Bizon  
Address Rt 1 Box 34017  
Hubbard Ore

**(2) TYPE OF WORK (check):**

New Well  Deepening  Reconditioning  Abandon   
If abandonment, describe material and procedure in Item 12.

**(3) TYPE OF WELL:**

Rotary  Driven   
Cable  Jetted   
 Bored

**(4) PROPOSED USE (check):**

Domestic  Industrial  Municipal   
Irrigation  Test Well  Other

**CASING INSTALLED:**

Threaded  Welded   
10" Diam. from 0 ft. to 162 ft. Gage .250  
" Diam. from " ft. to " ft. Gage "  
" Diam. from " ft. to " ft. Gage "

**PERFORATIONS:**

Perforated?  Yes  No.  
Type of perforator used STAR  
Size of perforations 1/4 in. by 3/8 in.  
640 perforations from 122 ft. to 138 ft.  
280 perforations from 150 ft. to 157 ft.  
perforations from " ft. to " ft.

**(7) SCREENS:**

Well screen installed?  Yes  No  
Manufacturer's Name .....  
Type ..... Model No. ....  
Diam. Slot size Set from " ft. to " ft.  
Diam. Slot size Set from " ft. to " ft.

**(8) WELL TESTS:**

Drawdown is amount water level is lowered below static level  
Was a pump test made?  Yes  No If yes, by whom? DRILLER  
Flow: 750 gal./min. with 44 ft. drawdown after 5 1/2 hrs.  
500 " 31 " 5 1/2 "  
" 300 " 18 " 5 1/2 "  
Baller test gal./min. with " ft. drawdown after " hrs.  
Artesian flow g.p.m.  
Temperature of water 51 Depth artesian flow encountered " ft.

**(9) CONSTRUCTION:**

Well seal—Material used Cement  
Well sealed from land surface to 21 ft.  
Diameter of well bore to bottom of seal 16 in.  
Diameter of well bore below seal 10 in.  
Number of sacks of cement used in well seal 13 sacks  
How was cement grout placed? TOP

Was a drive shoe used?  Yes  No Plugs ..... Size: location " ft.  
Did any strata contain unusable water?  Yes  No  
Type of water? " depth of strata  
Method of sealing strata off  
Was well gravel packed?  Yes  No Size of gravel: "  
Gravel placed from " ft. to " ft.

**(10) LOCATION OF WELL:**

County MARION Driller's well number  
NE 1/4 SE 1/4 Section 23 T. 45 R. 1 W. W.M.  
Bearing and distance from section or subdivision corner

**(11) WATER LEVEL: Completed well.**

Depth at which water was first found 122 ft.  
Static level 22 ft. below land surface. Date Oct 30  
Artesian pressure lbs. per square inch. Date

**(12) WELL LOG:**

Diameter of well below casing .....  
Depth drilled 162 ft. Depth of completed well 162 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOPSOIL	0	2	
CLAY BROWN	2	12	
SILT BROWN	12	16	
CLAY GREY	16	66	
SILT DARK GREY	66	73	
CLAY DARK BLUE STICKEY	73	81	
SILT DARK GREY	81	89	
CLAY BLUE GREY	89	105	
SILT SAND GREY	105	109	
CEMENT GRAVEL GREY	109	122	
GRAVEL MEDIUM BLACK	122	138	
SAND BLACK	138	143	
FINE SAND	143	146	
SILT GREY	146	148	
SAND & GRAVEL	148	159	
CLAY BLUE	159	162	

Work started Oct 24 19 78 Completed Nov 2 19 78  
Date well drilling machine moved off of well Nov 2 19 78

**Drilling Machine Operator's Certification:**

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Richard J Beck Date Nov 2, 19 78  
(Drilling Machine Operator)

Drilling Machine Operator's License No. 1200

**Water Well Contractor's Certification:**

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name J W Beck Well Drilling  
(Person, firm or corporation) (Type or print)

Address 24437 S Skyline Dr Canby Ore

[Signed] John W Beck  
(Water Well Contractor)

Contractor's License No. 1749 Date Nov 2, 19 78