

STATE ENGINEER
Salem, Oregon

Well Record

STATE WELL NO. 4/1W-23J
COUNTY Marion
APPLICATION NO. GR-1788

GR- 1730

OWNER: W. R. Newmyer

MAILING

ADDRESS: 4230 Shoreline Dr.

CITY AND

STATE: Salem, Oregon

LOCATION OF WELL: Owner's No.

NE 1/4 SE 1/4 Sec. 23 T. 4 S. R. 1 W., W.M.

Bearing and distance from section or subdivision

corner From SE cor. David Cochran DIC #51 - 464.3'

N. 01° W.; 1600' S. 89° 45' W.; 150' N. 01° W.

Altitude at well

180

TYPE OF WELL: Drilled Date Constructed 1949

Depth drilled 129' Depth cased 129'

CASING RECORD:

8"

FINISH:

Perforated from 116 to 125 ft.

AQUIFERS:

Gravel & sand from 116 to 125.

WATER LEVEL:

60' - 1959

PUMPING EQUIPMENT: Type Turbine H.P. 10

Capacity 160 G.P.M.

WELL TESTS:

Drawdown 110 ft. after hours 125 G.P.M.

Drawdown ft. after hours G.P.M.

USE OF WATER Irrigation 37.5 acres Temp. °F. 19

SOURCE OF INFORMATION GR Record

DRILLER or DIGGER

ADDITIONAL DATA:

Log Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

Log: Clay 0 to 40 ft.
Quicksand 40 to 90 ft.
Clay 90 to 116 ft.
Gravel 116 to 125 ft.
Clay 125 to 129 ft.

Irrigation of 37.5 acres.

N 01 deg W 464.3
ft; A 89 deg
4 5 min W 1600 ft.
N 01 deg W 150 ft