

WATER WELL REPORT

STATE OF OREGON

RECEIVED

AUG 1 1983

State Well No.

7512w-21

WATER RESOURCES DEPT.
SALEM, OREGON

State Permit No.

(1) OWNER:

Name DARRELL & PATTIE HOSLERAddress 1523 63RD AVE NECity SALEMState OR 97301

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☐ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
 Rotary Mud ☐ Dug ☐ Irrigation ☐ Test Well ☐ Other ☐
 Cased ☒ Bored ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐

(4) PROPOSED USE (check):

CASING INSTALLED: Steel ☒ Plastic ☐
 Threaded ☐ Welded ☒
 6" Diam. from 0' ft. to 92' ft. Gauge 4"
 " Diam. from " ft. to " ft. Gauge "

LINER INSTALLED:

" Diam. from " ft. to " ft. Gauge "

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
 perforations from " ft. to " ft.
 perforations from " ft. to " ft.
 perforations from " ft. to " ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.
 Diam. Slot Size Set from " ft. to " ft.
 Diam. Slot Size Set from " ft. to " ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

a pump test made? ☒ Yes ☐ No If yes, by whom? R. J. SNEED
25 gal./min. with 25 ft. drawdown after 1 1/2 hrs.

Air test gal./min. with drill stem at " ft. hrs.

Bailer test 30 gal./min. with 32 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water 57° Depth artesian flow encountered " ft.

(9) CONSTRUCTION:

Special standards: Yes ☒ No ☐Well seal—Material used BENTONITEWell sealed from land surface to 30 ft.Diameter of well bore to bottom of seal 10 in.Diameter of well bore below seal 6 in.Number of sacks of cement used in well seal NONE sacksHow was cement grout placed? CONDUCTOR PIPEWas pump installed? YES Type SUB HP 1 Depth 89 ft.Was a drive shoe used? ☒ Yes ☐ No Plugs NONE Size: location " ft.Did any strata contain unusable water? ☒ Yes ☐ NoType of Water? SURFACE depth of strata 20'Method of sealing strata off CASEDWas well gravel packed? ☐ Yes ☒ No Size of gravel: "

Gravel placed from " ft. to " ft.

(10) LOCATION OF WELL:

County MARION

Driller's well number

1/4 1/4 Section 21 T. 7S R. 2W W.M.Tax Lot # Lot 12 Blk SubdivisionAddress at well location: 1523 63RD NE SALEM OREAST SIDE FRUIT FARMS

(11) WATER LEVEL: Completed well.

Depth at which water was first found 90' TO 92' ft.Static level 46' ft. below land surface. Date 7-26-83

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing 6"Depth drilled 92 ft. Depth of completed well 92 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOPSOIL	0	1	
CLAY YELLOW COLOR	1	28	
CLAY BLUE STICKY	28	32	
BLUE CLAY SANDY FINE	32	42	
CLAY YELLOW STICKY	42	62	
CONGLOMERATE HARD	62	71	
CLAY YELLOW STICKY	71	72	
CONGLOMERATE	72	77	
CLAY YELLOW SANDY	77	78	
SAND BROWN MED TO FINE	78	79	
SAND & GRAVEL 1"	79	81	
CONGLOMERATE	81	91	
GRAVEL 1" + COARSE SAND	91	92	46

Work started 7-20 19 83 Completed 7-26-1983
 Date well drilling machine moved off of well 7-29 19 83

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] R. J. SNEED Date 7-29-1983
 (Drilling Machine Operator)

Drilling Machine Operator's License No. 187

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name R. J. SNEED WELL DRILLING
 (Person, firm or corporation) (Type or print)

Address 4750 ELIZABETH N. SALEM, OR.

[Signed] R. J. SNEED
 (Water Well Contractor)

Contractor's License No. 6 Date 7-29-1983

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT

SALEM, OREGON 97301

30 days from the date of well completion