

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

RECEIVED

AUG 16 1974

State Well No.

75/2W-28

STATE ENGINEER

State Permit No.

6-6211

SALEM, OREGON

(1) OWNER:

Name Carl Bendixsen
Address 2905 Walker Rd NE
Salem Ore 97303

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
10" Diam. from +1 ft. to 100 ft. Gage 0.25
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☒ Yes ☐ No.

Type of perforator used Mills
Size of perforations 3/8" in. by 2 1/2 in.
80 perforations from 70 ft. to 76 ft.
128 perforations from 88 ft. to 98 ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: 300 gal./min. with 10 ft. drawdown after hrs.
" " " "

Bailer test 50 gal./min. with 10 ft. drawdown after 1 hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Well seal—Material used Bentonite
Well sealed from land surface to 18' ft.
Diameter of well bore to bottom of seal 14 in.
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal sacks
Number of sacks of bentonite used in well seal 2 sacks
Brand name of bentonite National
Number of pounds of bentonite per 100 gallons
of water 30 lbs./100 gals.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County Marion Driller's well number
1/4 1/4 Section 28 T. 7S R. 2W W.M.

Bearing and distance from section or subdivision corner

(11) WATER LEVEL: Completed well.

Depth at which water was first found 54 ft.
Static level 37 ft. below land surface. Date 8/2/74
Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing

Depth drilled 100 ft. Depth of completed well 100 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Brown clay	0	31	
Grey clay	31	36	
Brown clay + gravel	36	54	
Mid gravel	54	56	
Clay + gravel	56	67	
fine to large gravel	67	76	
cemented gravel	76	85	
fine to large gravel with layers of clay	85	100	

Work started 7-22 19 74 Completed 8-2 19 74

Date well drilling machine moved off of well 8-2 19 74

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

(Signed) Harold L. Farrell Date 8/12, 19 74
(Drilling Machine Operator)

Drilling Machine Operator's License No. 455

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name Robinson's EOLAWELL Drilling
(Person, firm or corporation) (Type or print)

Address 4510 Dallas Rd N.W. Salem

(Signed) George H. Robinson
(Water Well Contractor)

Contractor's License No. 13 Date 8-12, 19 74