

NOTICE TO WATER WELL CONTRACTOR

The original and first copy
of this report are to be
filed with the

STATE ENGINEER, SALEM 10, OREGON
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON
(Please type or print)

State Well No. 7/2W-28

State Permit No. _____

(1) OWNER:

Name LeRoy Kuper
Address 540 Hampden Lane, N.E.
Salem, Oregon

(2) LOCATION OF WELL:

County Marion Driller's well number 62-19
1/4 1/4 Section 28 T. 7 S. R. 2 W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
Abandonment, describe material and procedure in Item 12.

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒

8" Diam. from 0 ft. to 1 1/4 ft. Gage .280
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Mills Knife

Size of perforations 3/8 in. by 1-1/4 in.
500 perforations from 68 ft. to 136 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Well seal—Material used in seal Drill mud from well
Depth of seal 1 1/4 ft. Was a packer used? yes
Diameter of well bore to bottom of seal 12 in.
Were any loose strata cemented off? ☐ Yes ☒ No Depth _____
Was a drive shoe used? ☒ Yes ☐ No
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ Depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level 43' 6" ft. below land surface Date 8/25/62
Artesian pressure _____ lbs. per square inch Date _____

(11) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom?

Yield:	280	gal./min. with	73	ft. drawdown after	3 1/2	hrs.
"	235	"	50	"	4	"
"	160	"	27	"	4	"

Ballor test	gal./min. with	ft. drawdown after	hrs.
Artesian flow			

Temperature of water _____ g.p.m. Date _____

Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well below casing 8"

Depth drilled 155 ft. Depth of completed well 155 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Brown clay	0	25
Brown sandy clay with few gravels and surface water	25	30
Heavy, light brown clay	30	45
Brown sand and coarse gravel with cementing clay	45	53
Brown sandy clay	53	63
Brown sand and coarse gravel partly cemented with tan clay (aquifer)	63	136
Heavy reddish tan clay	136	152
Solid red clay	152	155

Work started 8/14 19 62 Completed 8/25 19 62
Date well drilling machine moved off of well 8/25 19 62

(13) PUMP:

Manufacturer's Name _____
Type: _____ H.P. _____

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME West Well Drilling
(Person, firm or corporation) (Type or print)

Address 4098 Market Street, N.E., Salem

Drilling Machine Operator's License No. 188

[Signed] Marion E. West
(Water Well Contractor)

Contractor's License No. 30 Date 8/27, 19 62