

STATE OF OREGON  
**WATER WELL REPORT**  
 (as required by ORS 537.765)

DEC 28 1988  
**MARI 7997**  
 WATER RESOURCES DEPARTMENT  
 SALEM, OREGON

7997  
 MARI...  
 TS/2W/306d  
 SC 7811

**(1) OWNER:** Well Number: \_\_\_\_\_  
 Name Suburban E. Salem Water District  
 Address 115 Lancaster Drive N.E.  
 City Salem State OR Zip 97301

**(2) TYPE OF WORK:**  
 New Well  Deepen  Recondition  Abandon

**(3) DRILL METHOD**  
 Rotary Air  Rotary Mud  Cable  
 Other \_\_\_\_\_

**(4) PROPOSED USE:**  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Other \_\_\_\_\_

**(5) BORE HOLE CONSTRUCTION:**  
 Final Construction approval Yes No  
 Yes  No  No  Yes  
 Depth of Completed Well 178 ft.  
 Explosives used   Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
5	0	30	cement	0	30	170 bags
12	30	178	—	—	—	—

How was seal placed: Method  A  B  C  D  E  
 Other \_\_\_\_\_  
 Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
 Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

**(6) CASING/LINER:**

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 12"	0	178	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 178'

**PERFORATIONS/SCREENS:**

Perforations Method air perf.  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot size	Number	Tele/pipe diameter	Case	Liner
10	178	1/2"	2400	P	<input checked="" type="checkbox"/>	<input type="checkbox"/>

**(8) WELL TESTS: Minimum testing time is 1 hour**

Pump  Bailer  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
<del>240</del> 200		178	1 hr. 24 hrs

Temperature of water \_\_\_\_\_ Depth Artesian Flow Found \_\_\_\_\_  
 Was a water analysis done?  Yes By whom \_\_\_\_\_  
 Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
 Depth of strata: \_\_\_\_\_

**(9) LOCATION OF WELL by legal description:**  
 County Marion Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
 Township 7S N or S, Range 2W E or W, WM.  
 Section 30 SE  $\frac{1}{4}$  NW  $\frac{1}{4}$   
 Tax Lot \_\_\_\_\_ Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
 Street Address of Well (or nearest address) E & S of 422 Auburn Rd  
Salem, OR 97301

**(10) STATIC WATER LEVEL:**  
 \_\_\_\_\_ ft. below land surface. Date 12-9-88  
 Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

**(11) WATER BEARING ZONES:**  
 Depth at which water was first found 104'

From	To	Estimated Flow Rate	SWL
158	176	200	12'

**(12) WELL LOG:** Ground elevation \_\_\_\_\_

Material	From	To	SWL
Topsoil	0	1	
Clay brown med.	1	17	
Clay grey med sandy	17	35	
Cemented gravels	35	82	
Clay & gravels brown	82	104	
Sand & gravel brown med	104	158	
Sand & gravel coarse	158	176	

Date started 12-1-88 Completed 12-9-88

**(unbonded) Water Well Constructor Certification:**  
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.  
 Signed [Signature] WWC Number 1358  
 Date 12-27-88

**(bonded) Water Well Constructor Certification:**  
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.  
 Signed [Signature] WWC Number 723  
 Date 12-27-88

**MARI 7997**

**For Official Use Only:**

Received Date: \_\_\_\_\_

County Well Log ID #

Well Identification Tag #

MARI 7997

37893

## WELL IDENTIFICATION APPLICATION FORM

Michael J. Kurtz, Manager

### BUYER/CURRENT WELL OWNER:

**RECEIVED**

Name: Suburban East Salem Water District

USER ID 12466

DEC 14 1999

Mailing Address: 3805 LaBranch Street SE

**WATER RESOURCES DEPT.  
SALEM, OREGON**

City: Salem

State: Oregon Zip: 97301

Phone: (503) 364-1620

### WELL LOCATION:

MARI 7997

County: Marion

Owner's Well Number: Well 2A

Township: 7 N of (S) Range: 2 E of (W) Section: 30 SE 1/4 NW 1/4

Tax Lot Number: 1902 Type of Well: water supply Domestic monitoring \_\_\_\_\_

Street Address of Well (if different from above): Behind 4122 Auburn Rd NE Salem, OR  
ORS 264

### WELL INFORMATION: (do not complete remainder of application if well log is available)

WELL LOG ATTACHED

Start Card Number: \_\_\_\_\_ Approx. Construction Date: \_\_\_\_\_

Well Constructor: \_\_\_\_\_

Name of Owner at Time of Construction: \_\_\_\_\_

Well Depth (in feet): \_\_\_\_\_ Static Water Level (in feet): \_\_\_\_\_

Diameter of Exposed Well Casing (in inches): \_\_\_\_\_

Does this well have a formal water right associated with it? Yes: \_\_\_\_\_ No: \_\_\_\_\_

If Yes: Application #: \_\_\_\_\_ Permit #: \_\_\_\_\_ Certificate #: \_\_\_\_\_

Please Return Completed Form to:

**Larry D. McQueen  
Well Identification Program  
Oregon Water Resources Department  
158 12th Street NE  
Salem, OR 97310**