

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED
OCT 28 1987
WATER RESOURCES DEPT.
SALEM, OREGON

8919
MAY 31 1988

891W-29ab

(1) OWNER:

Name Mike Knox
Address 10945 Jamesway Dr.
City Amesville State Or Zip 97325

Owner's Well Number: 764

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Depth of Completed Well 270 ft.

Special Standards date of approval _____

HOLE		SEAL		Amount	
Diameter	From To	Material	From To	sacks or pounds	
10"	0 20	Concrete	0 20	7 Sacks	
8"	20 180				
6"	180 270				

How was seal placed? Method ☐ A ☐ B ☒ C ☐ D ☐ E

☐ Other _____

Backfill placed from _____ ft. to _____ ft. Material _____

Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	6"	0	180	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:	4"	0	270	160	☐	☒	☒	☐
					☐	☐	☐	☐

Location of shoe(s) _____

(7) PERFORATIONS/SCREENS:

☒ Perforations Method Sk. 1 Saw
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
210	270	1/4" x 7/8"	75			☐	☒
						☐	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

Yield gal/min	Pumping level	Drill stem at	Time 1/2 hr
100		265	4hr
			1 hr

Temperature of water _____ Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☒ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County Marion Latitude _____ Longitude _____
Township 8S N or S, Range 1W E or W, WM.
Section 29 N.W. 1/4 N.E. 1/4
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) 10935 Jamesway
Amesville, Or - 97325

(10) STATIC WATER LEVEL:

110 ft. below land surface. Date Oct. 17, 1987

Artesian pressure _____ lb. per square inch. Date _____

(11) WELL LOG:

Ground elevation _____

Material	From	To	WB?	SWL
Soil	0	2		
Clay Small Gravel Drump	2	10		
Clay	10	25		
Clay Small Gravel	25	27		
Clay	27	55		
Clay Small Gravel	55	60		
Clay Red	60	90		
Grdy Clay	90	122		
Claystone Blue	122	153		
Claystone Brown	153	172		
Claystone Black	172	249		
Grdy V. Hard	249	260		
Rock	260	267		110
Rock Very Hard	267	270		

Date started Oct. 9, 1987 Completed Oct. 17, 1987

(unbonded) Water Well Constructor Certification:

I constructed this well in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed William Long Date Oct. 17, 1987

(bonded) Water Well Constructor Certification:

I accept responsibility for construction of this well and its compliance with all Oregon water well standards. This report is true to the best of my knowledge and belief.

Signed William Long Date Oct. 17, 1987

Company William Long Drilling Co. Job No. _____