

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON within 30 days from the date of well completion.

RECEIVED
STATE ENGINEER
SALEM, OREGON

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

Do not write above this line

RECEIVED
NOV 12 1968

STATE ENGINEER

Ph-989-8456

State Well No.

State Permit No.

2/24-36 R

(1) OWNER:

Name TERRAL BENGE
Address Heppner, Oregon

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Aug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒

14" Diam. from 0 ft. to 20 ft. Gage 250
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? ☐ Yes ☒ No

Type of perforator used

Size of perforations in. by in.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 40' ft. below land surface Date July 9
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?

Yield: gal./min. with ft. drawdown after hrs.
air tested 300 GPM

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m. Date

Temperature of water 63° Was a chemical analysis made? ☐ Yes ☒ No

(10) CONSTRUCTION:

Well seal—Material used Cement GROUT
Depth of seal 20' ft.

Diameter of well bore to bottom of seal 20' in.

Were any loose strata cemented off? ☐ Yes ☒ No Depth

Was a drive shoe used? ☐ Yes ☐ No

Did any strata contain unusable water? ☐ Yes ☐ No

Type of water depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel:

Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County Morrow Driller's well number

S.E. 1/4 NE 1/4 Section 36 T. 25. R. 24 E. W.M.

Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 12" 250' 400'

Depth drilled 400' ft. Depth of completed well 400' ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

MATERIAL	From	To	SWL
TOP Soil	0	3	
COURSE GRAVEL	3	9	
BOULDERS	9	18	
Rock DK Grey	18	20	
Red & Black Broken Rock	20	25	
Red Rock-Watch	25	80	
Grey Rock	80	125	
Pink Stone Soft			
Red Rock	125	150	40'
Grey Rock	150	170	
" "	170	240	
Red Cinder	240	260	
Brown Rock Soft	260	295	
Grey Rock	295	400	40'

Work started July 8 1968 Completed July 19 1968

Date well drilling machine moved off of well July 19 1968

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] William A. Kuehn Date July 19, 1968
(Drilling Machine Operator)

Drilling Machine Operator's License No. 524

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Roy T. French
(Person, firm or corporation) (Type or print)

Address Rte 2, Box 129

[Signed] Roy T. French
(Water Well Contractor)

Contractor's License No. 107 Date Sept 10, 1969