

STATE ENGINEER, BALEM, OREGON files within 90 days from the date of well completion.

(Please type or print)

State Permit No.

MORR 1251

G-5633

Permit No 1

(1) OWNER:

Name: Debra's Health, Inc. Address: 110 1/2 Ave 216

(2) TYPE OF WORK (check):

New Well Reopening Reconditioning Abandon

(3) TYPE OF WELL:

Drives Cased Dug

(4) PROPOSED USE (check):

Domestic Industrial Municipal Irrigation Test Well Other

(5) CASING INSTALLED:

Diam. from 0 ft. to 131 ft. Gage 50

(6) PERFORATIONS:

Type of perforator used: Machine. Size of perforations: 7/16 in. by 3 in. Perforations from 91 ft. to 131 ft.

(7) SCREENS:

Well screen installed? Yes No. Material: 20 mesh. Slot size: 1/16 in.

(8) PUMP TESTS:

Was a pump test made? Yes No. Field: 137V. Drawdown in ambient water level in 24 hrs. 34 ft.

(9) CONSTRUCTION:

Well wall material used: Cement. Diameter of well bore to bottom of seal: 24 in. Number of sacks of cement used: 98. Brand name of bentonite: ...

(10) LOCATION OF WELL:

County: MORRIS. Driller's well number: NE 1/4 SE 1/4 Section 27 T. 5 S. R. 26 E. Bearing and distance from section or subdivision corner: 1320' West of 1/4 corner 26/27 10 S

(11) WATER LEVEL: Completed well.

Depth at which water was first found: 57. Static level: 57 ft. below land surface. Date: 5-21. Artesian pressure: lbs. per square inch. Date:

(12) WELL LOG:

Diameter of well below casing: 131. Depth drilled: 131. Depth of completed well: 131. Formation: Describe color, texture, grain size and structure of material and show thickness and nature of each stratum and aquifer penetrated with at least one entry for each change of formation.

Table with columns: MATERIAL, From, To. Rows: Top soil (0-4), Sandy clay (4-7), coarse sand & fine gravel (7-32), gravel & boulders (32-37), gravel, boulders & fine sand (37-131).

Work started: 9-11 1971. Completed: 6-1 1972. Date well drilling machine moved off of well: 7-23 1972.

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to the best of my knowledge and belief. (Signed) [Signature] Date: 7/1/72

Drilling Machine Operator's License No. 755

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report true to the best of my knowledge and belief. Name: [Signature] Address: 1240 N. 1st St. (Signed) [Signature] Contractor's License No. [Signature]