



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

Well #F Big Dad
Permit G-16951

Do not complete if the well already has a Well I.D. Number.

I. OWNER INFORMATION

Current Owner Name (please print): Alan Cleaver
Mailing Address: P.O. Box 1191
City: Hermiston State: OR Zip: 97838
Mailing Address (to send Well I.D.): P.O. Box 1191
City: Hermiston State: OR Zip: 97838

II. WELL INFORMATION (Do not complete this section if the well report is attached.)

Township: 5 North (North/South) Range: 26 East (East/West) Section: 34
Tax Lot: 100 County: Morrow SE 1/4 NW 1/4
Street Address of Well: N/A City: N/A
Owner at time the well was constructed, (if known): Desert Magic, Inc
If the property had a different street address in the past: N/A

III. GENERAL WELL INFORMATION (Do not complete this section if the well report is attached)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Irrigation
Date Well Constructed: 8-20-1971 Total Well Depth: Casing Diameter:
Other Information: Please refer to attached Well Log Morr 1271

SUBMITTED BY (please print): Bill Porfily
PHONE: (541) 449-1327 FAX: (541) 449-1327

RECEIVED

MAR 07 2013

WATER RESOURCES DEPT
SALEM, OREGON

Send application to Oregon Water Resources Department; 725 Summer St NE, Suite A; Salem, Oregon 97301-1266; fax (503) 986-0902. Applications are processed and Well I.D. Numbers are mailed every Wednesday.

For Official Use Only by the Oregon Water Resources Department:

Received Date: 3-7-13 Well Log Number: MORR 1271 Well Identification #: L 111230

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310 within 30 days from the date of well completion.

MORR 1271

NC 10 RECEIVED WATER WELL REPORT STATE OF OREGON NOV 19 1971 STATE ENGINEER (Please type NAME OF CONTRACTOR) MORR 1271 Well No 10

State Well No. 52465-34d6c

State Permit No. Well F Big D Dad

(1) OWNER:

Name DESERT MAGIC, INC. #10 Address P.O. Box 216 Boardman Oregon

(2) TYPE OF WORK (check):

New Well [x] Deepening [] Reconditioning [] Abandon []

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary [x] Driven [] Cable [] Jetted [] Dug [] Bored []

(4) PROPOSED USE (check):

Domestic [] Industrial [] Municipal [] Irrigation [x] Test Well [] Other []

CASING INSTALLED:

16" Diam. from 0 ft. to 52 ft. Gage 250

PERFORATIONS:

Type of perforator used Size of perforations in. by in. perforations from ft. to ft.

(7) SCREENS:

Well screen installed? [x] Yes [] No Manufacturer's Name Johnson Type Model No. Diam. 16 Slot size 50 Set from 42 ft. to 52 ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level Was a pump test made? [x] Yes [] No Yield: 628 gal./min. with 22 ft. drawdown after 8 hrs.

(9) CONSTRUCTION:

Well seal-Material used cement Well sealed from land surface to 32 ft. Diameter of well bore to bottom of seal 24 in. Number of sacks of cement used in well seal 52 sacks

(10) LOCATION OF WELL:

County Morrow Driller's well number NW 1/4 SE 1/4 Section 34 T. 5N R. 26E W.M. Bearing and distance from section or subdivision corner 1600' North & 1850' West of the SE corner Section 34

(11) WATER LEVEL: Completed well.

Depth at which water was first found 32 ft. Static level 32 ft. below land surface. Date 8-20-71 Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing Depth drilled 52 ft. Depth of completed well 52 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation.

Table with columns: MATERIAL, From, To, SWL. Rows include top soil - brown sandy, coarse sand & gravel, sand gravel & boulders, basalt.

Work started 8-15 1971 Completed 8-20 1971 Date well drilling machine moved off of well 8-20 1971

Drilling Machine Operator's Certification: This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief. [Signed] Steve Morris Date Oct 17, 1971

Water Well Contractor's Certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Name Desert Magic, Inc. Address Box 216, Boardman, Ore. 97818 [Signed] Thruval Kesteven, Pres. Contractor's License No. Date 10-19 71