

APR 27 1990

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

WATER RESOURCES DEPT.
SALEM, OREGON

MORR 1504 2N/26E/500
(START CARD) # 18681

(1) OWNER: Well Number: _____
Name Finley Buttes Landfill Co.
Address 6 Southeast Beach Drive
City Vancouver State WA Zip 98661-7198

(2) TYPE OF WORK:
 New Well Deepen Recondition Abandon

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable
 Other _____

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 745 ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
15"	0	309	Cement	0	309	500 sacks
10"	309	745				

How was seal placed: Method A B C D E
 Other _____
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

Casing/ Liner:	Diameter	From	To	Gauge	Steel		Plastic		Welded		Threaded	
					✓		✓		✓		✓	
Casing:	10"	72	309	.250	✓				✓			
Liner:												

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:
 Perforations Method _____
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>
						<input type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailor Air Flowing Artesian
Yield gal/min 300 Drawdown _____ Drill stem at 745 Time 1 hr.

Temperature of water _____ Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Morrow Latitude _____ Longitude _____
Township 2N N or S, Range 26E E or W, WM.
Section 5 SE ¼ NE ¼
Tax Lot 301 Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) Bombing Range Rd. Boardman, OR 97818

(10) STATIC WATER LEVEL:
318 ft. below land surface. Date 4-4-90
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 481

From	To	Estimated Flow Rate	SWL
481	490	40	290
501	523	60	290
630	645	100	307
701	745	100	318

(12) WELL LOG: Ground elevation _____

Material	From	To	SWL
Brown silty soil	0	4	
Gray ash	4	9	
Sandy brown clay	9	84	
Brown clay, some gravel	84	219	
Soft gray basalt, some green soapstone	219	301	
Gray basalt	301	481	
Gray basalt with green soapstone	481	490	WB
Gray basalt	490	501	
Gray basalt with green soapstone	501	523	WB
Gray basalt	523	630	
Gray basalt with green soapstone	630	645	WB
Gray basalt	645	701	
Brown & gray basalt with green soapstone	701	745	WB

Date started 3-20-90 Completed 4-4-90

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

WWC Number _____
Signed _____ Date _____

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1218
Signed Patrick C. Wallace Date 4-16-90