

WATER WELL REPORT

WATER RESOURCES DEPARTMENT
SALEM, OREGON 97310
within 30 days from the date
of well completion.

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 35/25E-34d

State Permit No. _____

(1) OWNER:

Name Harold Wright
Address Rt 1
Heppner Oregon 97836

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
Cable ☐ Jetted ☐
Dug ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

CASING INSTALLED:

Threaded ☐ Welded ☒
10" Diam. from 14 ft. to 57 ft. Gage 250
" Diam. from " ft. to " ft. Gage "
" Diam. from " ft. to " ft. Gage "

PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations	in. by	in.
perforations from	ft. to	ft.
perforations from	ft. to	ft.
perforations from	ft. to	ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

Was a pump test made? ☐ Yes ☒ No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.
" " " " " "
" " " " " "
AIR 500 gal./min. with 345 ft. drawdown after 1 hrs.
Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used Cement
Well sealed from land surface to 57 ft.
Diameter of well bore to bottom of seal 12 in. 14" to 20"
Diameter of well bore below seal 10 in.
Number of sacks of cement used in well seal 25 sacks
How was cement grout placed? Pressure grouted

Was a drive shoe used? ☐ Yes ☒ No Plugs _____ Size: location _____ ft.
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ depth of strata _____
Method of sealing strata off _____
Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Morrow Driller's well number _____
1/4 SE 1/4 Section 34 T. 38 R. 25E W.M.
Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 32 ft.
Static level 55 ft. below land surface. Date 8-13-79
Artesian pressure lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 10" to 400'
8" to 1750'

Depth drilled 750 ft. Depth of completed well 750 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
Topsail	0	7	
Basalt, broken	7	26	
Basalt, block	26	66	
Rock, black & green claystone	66	97	
Basalt,	97	145	
Rock, dark brown & green claystone	145	158	
Basalt	158	218	
Rock, brown & green claystone	218	229	W.B.
Basalt	229	495	
Basalt, hard gray	495	535	
Rock, brown & black & green clay.	535	550	W.B.
Basalt, black	550	685	
Basalt, hard, gray	685	722	
Rock, med. black & blue clay.	722	750	W.B.

RECEIVED

AUG 30 1979

WATER RESOURCES DEPT.

SALEM, OREGON
Work started 7-3 19 79 Completed 8-13 19 79
Date well drilling machine moved off of well 8-13 19 79

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] James T. Litch Date 8-13, 19 79
(Drilling Machine Operator)

Drilling Machine Operator's License No. 665

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name TRAY GRIFFIN
(Person, firm or corporation) (Type or print)

Address 900 HERMISTON AVE, HERMISTON ORE.

[Signed] Tray Griffin
(Water Well Contractor)

Contractor's License No. 65 Date 8-13, 19 79