

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

AUG 18 1997

WELL I.D.# L 13797

(START CARD) # 98330

Instructions for completing this report are on the last page of this form.

WATER RESOURCES DEPT.

SALEM, OREGON

(1) OWNER:

Well Number

Name Jerry Ripha
Address 16220 McBea Rd 65040 17 74
City Long State OR Zip 97738

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 231 ft.

Explosives used ☐ Yes ☒ No Type Amount

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
12	0	39	P70 Cem	0	39	29 545
8	39	231				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	8	+1	39	25	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

		Method		Type		Material		Tele/pipe		Liner	
		From	To	Slot size	Number	Diameter	Size	From	To	From	To
RECEIVED SEP 25 1997 WATER RESOURCES DEPT. SALEM, OREGON											

(8) WELL TESTS: Minimum testing time is 1 hour

		Method		Type		Material		Tele/pipe		Liner	
		From	To	Slot size	Number	Diameter	Size	From	To	From	To
RECEIVED SEP 25 1997 WATER RESOURCES DEPT. SALEM, OREGON											

Temperature of water 52 Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata:

(9) LOCATION OF WELL by legal description:

County Marion Latitude Longitude
Township 1 ☒ N or S Range 23 ☒ E or W. WM.
Section 34 SE 1/4 SWSE 1/4
Tax Lot 690 Lot Block Subdivision
Street Address of Well (or nearest address)

(10) STATIC WATER LEVEL:

8 ft. below land surface. Date 7-21-97
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 76

From	To	Estimated Flow Rate	SWL
76	81	15	8
94	102	200	8
176	185	250	8
202	206	300	8
218	227	450	8

(12) WELL LOG:

Ground Elevation 900'

Material	From	To	SWL
sail	6	3	
cemented gravel	3	19	
Brown Basalt	19	24	
Black Basalt	24	28	
gray	28	34	
Brown	34	35	
gray	35	76	
Brown	76	81	
gray	81	94	
Brown scoria	94	102	
gray	102	176	
Brown	176	185	
gray	185	200	
Brown w/ fine claystone	200	206	
gray	206	218	
red & brown scoria	218	227	
gray	227	231	

Date started 7-17-97 Completed 7-21-97

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number 1683

Signed Tony Bowmen Date 7-21-97

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 544

Signed Jerry Bunn Date 7-21-97