

STATE OF OREGON WATER SUPPLY WELL REPORT

(as required by ORS 537.765)

 WELL I.D. # L 61452
 START CARD # 151939

Instructions for completing this report are on the last page of this form.

 (1) LAND OWNER GERALD WILSON Well Number 1
 Name GERALD WILSON
 Address 67208 HWY 74
 City TONE State OR Zip 97843

 (2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

 (3) DRILL METHOD:
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Other _____

 (4) PROPOSED USE:
☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other _____

 (5) BORE HOLE CONSTRUCTION:
 Special Construction approval ☐ Yes ☒ No Depth of Completed Well 241 ft.
 Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Sacks or pounds
Diameter	From	To	Material	From	To	
14"	0	22'	Cement	0	22'	14 SACKS
10"	22	241				

 How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other _____

 Backfill placed from _____ ft. to _____ ft. Material _____
 Gravel placed from _____ ft. to _____ ft. Size of gravel _____

 (6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	10"	+2	22	250	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
					☐	☐	☐	☐
Liner:					☐	☐	☐	☐
					☐	☐	☐	☐

 Drive Shoe used ☐ Inside ☐ Outside ☒ None
 Final location of shoe(s) _____

 (7) PERFORATIONS/SCREENS:
☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐

 (8) WELL TESTS: Minimum testing time is 1 hour
☐ Pump ☐ Bailer ☒ Air ☐ Flowing
☐ Artesian

Yield gal/min	Drawdown	Drill stem at	Time
300+		241	1 hr.

 Temperature of water 54° Depth Artesian Flow Found _____
 Was a water analysis done? ☐ Yes By whom _____
 Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
 Depth of strata: _____

 (9) LOCATION OF WELL by legal description:
 County MORROW Latitude _____ Longitude _____
 Township 1N N or S Range 23E E or W. WM.
 Section 22 NW 1/4 NW 1/4
 Tax Lot 2901 Lot _____ Block _____ Subdivision _____
 Street Address of Well (or nearest address) 67208 Hwy 74
TONE OR. 97843

 (10) STATIC WATER LEVEL:
134 ft. below land surface. Date 10-15-02
 Artesian pressure _____ lb. per square inch Date _____

 (11) WATER BEARING ZONES:
 Depth at which water was first found 160'

From	To	Estimated Flow Rate	SWL
160	171	75 gpm	134
200	230	200 gpm	134

 (12) WELL LOG:
 Ground Elevation _____

Material	From	To	SWL
Soil	0	16	
Black Basalt	16	35	
Grey Basalt	35	97	
Brown Basalt	97	110	
Black Basalt	110	140	
Black w/ green claystone	140	155	
Brown/Tan claystone	155	160	
Black	155	160	
Brown/Tan Claystone	160	171	134'
Black	171	200	
Brown scoria	200	230	134'
Black Basalt	230	241	

RECEIVED

OCT 23 2002

WATER RESOURCES DEPT.
SALEM, OREGON

 Date started 10-14-02 Completed 10-15-02
 (unbonded) Water Well Constructor Certification:
 I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.
 Signed [Signature] WWC Number 1735
 Date 10-15-02

 (bonded) Water Well Constructor Certification:
 I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
 Signed [Signature] WWC Number 544
 Date 10-15-02