

STATE OF OREGON
WATER SUPPLY WELL REPORT

MORR 53253

WELL I.D. LABEL# L

Page 1 of 3

157163

START CARD #

1082724

ORIGINAL LOG #

(as required by ORS 537.545 & 537.765 and OAR 690-205-0210)

7/23/2026

(1) LAND OWNER

Owner Well I.D.

First Name ANDREW

Last Name TIMPY

Company

Address 75585 PHEASANT LN

City IRRIGON

State OR

Zip 97844

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion

☐ Alteration (complete 2a & 10) ☐ Abandonment (complete 5a)

(2a) PRE-ALTERATION

Casing: Dia + From To Gauge Stl Plstc Wld Thrd
Material From To Amt sacks/lbs
Seal: Material From To Amt sacks/lbs

(3) DRILL METHOD

☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☒ Domestic ☐ Irrigation ☐ Community

☐ Industrial/ Commercial ☐ Livestock ☐ Dewatering
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard ☐ (Attach copy)

Depth of Completed Well 325.00 ft.

BORE HOLE			SEAL			Amt	sacks/ lbs
Dia	From	To	Material	From	To		
12	0	18	Cement	0	7	28	S
10.5	18	120	Calculated			2.33	
8	120	325	Bentonite	7	18	145	S
			Calculated			6.24	

Seal placement method: ☐ A ☒ B ☐ C ☐ D ☐ E ☒ Other: BENTONITE POURED

Backfill placed from ft. to ft. Material

Filter pack from ft. to ft. Material Size

Explosives used: ☐ Type Amount

Seal Placement Begin Date 7/9/2026 Begin Time 06 00

(5a) ABANDONMENT USING UNHYDRATED BENTONITE

Proposed Amount

Actual Amount

(6) CASING/LINER

C/L	Dia	+	From	To	Gauge	Mat. Type	Wld	Thrd	Shoe	Location
C	8	☒	2	120	0.250	ST	☒			
L	4.5		25	325	Sch80	PL		☒		

Temp casing ☐ Yes Dia From + To

(7) PERFORATIONS/SCREENS

Perforations Method skillsaw

Screens Type

Material

Perf/	Casing/	Screen			Scrn/slot	Slot	# of	Tele/
Screen	Liner	Dia	From	To	width	length	slots	Pipe size
Perf	Liner	4.5	290	325	.25	6	480	

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)
Air	40		287	1

Temperature 60 °F Lab analysis ☐ Yes By

Water quality concerns? ☐ Yes (describe below) TDS amount 155 ppm
From To Description Amount Units

(9) LOCATION OF WELL (legal description)

County MORROW Twp 5.00 N N/S Range 26.00 E E/W WM

Sec 36 SE 1/4 of the NE 1/4 Tax Lot 107

Tax Map Number Lot

Lat ° ' " or 45.87393070 DMS or DD

Long ° ' " or -119.49692540 DMS or DD

☒ Street address of well ☐ Nearest address

75585 PHEASANT LN
IRRIGON, OR 97844

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well / Pre-Alteration				
Completed Well	7/21/2026			95
Flowing Artesian?		☐	Dry Hole?	
		☐		

WATER BEARING ZONES

Depth water was first found 12.00

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
7/8/2026	12	16	2			12
7/13/2026	96	103	5			92
7/21/2026	279	287	40			95

(11) WELL LOG

Ground Elevation 356.46 FT

Material	From	To
silty sand	0	4
sand	4	15
brown clay/pea gravels	15	24
caliche and tan clay	24	32
black frac basalt	32	36
med black basalt	36	84
blue clay	84	96
black vesicular basalt	96	103
med black basalt	103	210
black and grey basalt	210	221
hard grey basalt	221	241
blue clay	241	279
black frac/broken basalt	279	287
brownish black frac	287	299
reddish brown frac	299	312
hard black basalt	312	319
hard grey basalt	319	325

Construction

Begin Date 7/8/2026 Begin Time 13 10 End Date 7/21/2026

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number Date

Signed

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 1766 Date 7/23/2026

Signed BRANDON BROWN (E-filed)

Drilling Company: Waterwell Developing & Surveys

ORIGINAL - WATER RESOURCES DEPARTMENT

THIS REPORT MUST BE SUBMITTED TO THE WATER RESOURCES DEPARTMENT WITHIN 30 DAYS OF COMPLETION OF WORK Form Version:

New exempt use wells must be submitted with a map and recording fee.

(2a) PRE-ALTERATION

Dia	+	From	To	Gauge	Stl	Plstc	Wld	Thrd

Material	From	To	Amt	sacks/lbs

(5) BORE HOLE CONSTRUCTION

BORE HOLE			SEAL			sacks/	
Dia	From	To	Material	From	To	Amt	lbs
			Cement	105	120	32	S
			Calculated			2.65	
			Calculated				
			Calculated				
			Calculated				
			Calculated				
			Calculated				

FILTER PACK			
From	To	Material	Size

(6) CASING/LINER

[illegible]

(7) PERFORATIONS/SCREENS

[illegible]

(8) WELL TESTS: Minimum testing time is 1 hour

Type of Test	Yield (gal/min)	Drawdown	Drill Stem/ Pump Depth	Duration (hr)

Water Quality Concerns

From	To	Description	Amount	Units

(10) STATIC WATER LEVEL

[illegible]

(11) WELL LOG

[illegible]

Name of person(s) who assisted with construction and Trainee License # / Helper #

Assistant Name	Type	#
HAIDEN DAY	HELPER WATER	8888942
ZANE ESTES	HELPER WATER	8889009
CLAYTON WRIGHT	HELPER WATER	8888969

Comments/Remarks

Shale trap packers for clay and centering. 27',285',295'

WATER SUPPLY WELL REPORT - Map with location identified must be attached and shall include an approximate scale and north arrow

MORR 53253

7/23/2026

Map of Hole

STATE OF OREGON WELL LOCATION MAP

This map is supplemental to the WATER SUPPLY WELL REPORT

Oregon Water Resources Department

725 Summer St NE, Salem OR 97301
(503)986-0900



LOCATION OF WELL

Latitude: 45.87393070 Datum: WGS84

Longitude: -119.49692540

Township/Range/Section/Quarter-Quarter Section:

WM5.00N26.00E36SENE

Address of Well:

75585 PHEASANT LN
IRRIGON, OR 97844

Well Label: 157163

Printed: July 23, 2026

DISCLAIMER: This map is intended to represent the approximate location the well. It is not intended to be construed as survey accurate in any manner.

Provided by well constructor

