

MULT 103417

MULT 103417

STATE OF OREGON WATER SUPPLY WELL REPORT (as required by ORS 537.765)

SKYLES DRILLING, INC. 503-656-2683

WELL ID # L ^{LOST!} 102694-130103 START CARD # W1011387

(1) OWNER: Well Number: 01 Name: Multnomah County/Geo Design, Inc/East County Proj. Address: c/o Property Management, 401 N. Dixon St. City: Portland State: OR Zip: 97227-1865

(2) TYPE OF WORK: [X] New Well [] Deepening [] Alteration (repair/recondition) [] Abandonment

(3) DRILL METHOD: [X] Rotary Air [] Rotary Mud [] Cable [] Auger [X] Other Holte

(4) PROPOSED USE: [] Domestic [] Community [] Industrial [] Irrigation [] Thermal [] Injection [] Livestock [X] Other Test

(5) BORE HOLE CONSTRUCTION: Special Construction approval [] Yes [X] No Depth of Completed Well 159 ft. Explosives used [] Yes [X] No Type Amount

Table with columns: HOLE Diameter, From, To, SEAL Material, From, To, Amount sacks or pounds. Row 1: 12, 0, 20, Cement w/5%, 20. Row 2: 9.6, 20, 159, Bentonite, 0, 23 Sacks.

How was seal placed: Method [] A [] B [X] C [] D [] E [] Other Backfill placed from ft. to ft. Material Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER: Diameter From To Gauge Steel Plastic Welded Threaded Casing: 8 +2 158 .250 [X] [] [X] [] Liner: None [] [] [] [] Drive Shoe used [] Inside [] Outside [X] None Final location of shoe(s)

(7) PERFORATIONS/SCREENS: [X] Perforations Method Air Perforator [] Screens Type Material From To Slot size Number Diameter Tele/pipe size Casing Liner

(8) WELL TESTS: Minimum testing time is 1 hour [] Pump [] Bailer [X] Air [] Flowing Artesian Yield gal/min Drawdown Drill stem at Time

Temperature of Water 54.5 Depth Artesian Flow found Was a water analysis done? [] Yes [] No By whom Did any strata contain water not suitable for intended use? [] Too little [] Salty [] Muddy [] Odor [] Colored [] Other Depth of strata:

(9) LOCATION OF WELL by legal description: County Multnomah Latitude Longitude Township 1SOUTH N or S. Range 3EAST E or W. of WM. Section 05BB NW 1/4 NW 1/4 Tax lot 2100 Lot Block Subdivision Street Address of Well (or nearest address) 18500 SE Stark St., Gresham, OR

(10) STATIC WATER LEVEL: 63.5 ft. below land surface. Date 9/15/2010 Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES: Depth at which water was first found 66'

Table with columns: From, To, Estimated Flow Rate, SWL. Row 1: 66, 85, 40, 63.5. Row 2: 107, 159, 175, 63.5.

(12) WELL LOG: Ground elevation

Table with columns: Material, From, To, SWL. Row 1: Asphalt & gravel, 0, .5. Row 2: Clay, brown w/ cobbles, .5, 3. Row 3: Gravel, medium w/ boulders, 3, 13. Row 4: Gravel, medium, tight @times, 13, 107. Row 5: Conglomerate, multicolored, 107, 159, 63.5.

RECEIVED

SEP 21 2010

WATER RESOURCES DEPT SALEM, OREGON

Skyles Drilling, Inc. 21912 S. Beaver Creek Rd. Oregon City, OR 97045 503-656-2683

Date started 9/8/2010 Completed 9/15/2010

(unbonded) Water Well Constructor Certification: I certify that the work performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1715 Date 9/15/2010 Skyles Drilling, Inc.

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed [Signature] WWC Number 1592 Date 9/15/2010 Skyles Drilling, Inc.



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

RECEIVED

MAR 23 2018

WATER RESOURCES DEPT
SALEM, OREGON

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): Multnomah County
Mailing Address: c/o Property Management, 401 N. Dixon Street
City, State, Zip: Portland, Oregon 97227
Mail Well ID Tag to: [] SAME AS ABOVE [X] In Care Of (C/O)
Name & Address: PBS Engineering and Environmental, attn: Chad Koepfle, 4412 SW Corbett Avenue
City, State, Zip: Portland, Oregon 97239

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 1S (North / South) Range: 3E (East / West) Section: 5 NW 1/4 of the NW 1/4
Tax Lot (usually last 3-5 numbers of Tax Map #): 2100 County Multnomah
GPS Coordinates:
Street Address of Well, City: 18480 SE Stark St., Gresham
If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Log, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): Test and geothermal
Date Well Constructed (or property built): 9/15/2010 Total Well Depth: 159 Casing Diameter: 8-inch
Owner at time the well was constructed (if known): Multnomah County Well Log # (if known): Mult 103417
Other Information: Requesting replacement well ID tag TAG # L-102694 LOST!
(placed by driller)

SUBMITTED BY (please print): Chad Koepfle
PHONE: 503.935.5501 EMAIL &/or FAX: Chad.koepfle@pbsusa.com

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

* Replacement Tag *

For Official Use Only by the Oregon Water Resources Department:
Received Date: 3-23-18 Well Log Number: MULT 103417 Well Identification #: L-130103