


Horizontal scale : $1'' = 5''$



Sponge Specifications

Polymer: Neoprene (Open Cell)

Hardness: SOFT (2-5 PSI for 25% defl.)

ASTM D1056-67 Grade SCO-11

Steel Band Spacing:

1 at top of packer

1 at bottom of packer

1 in middle of packer.

Notes:

1. Abrade outside skin of sponge to allow w. penetration.
2. Work air bubbles out of sponge as it is lowered into the well.
3. Do not set bands so tight that they cut the rubber.
4. All band material is stainless steel.