

STATE ENGINEER  
Salem, Oregon

MULT Well Record  
001316

STATE WELL NO. 1N/3-23B  
COUNTY Multnomah  
APPLICATION NO. GR-4163

OWNER: Bonneville Power Administration

MAILING ADDRESS: P.O. Box 3537

LOCATION OF WELL: Owner's No. \_\_\_\_\_

CITY AND STATE: Portland 8, Oregon

NW 1/4 NE 1/4 Sec. 23 T. 1 N. X, R. 3 E. W, W.M.

Bearing and distance from section or subdivision  
corner N. 27°34'10" W. 4642.0 ft. from SE Cor. Sec. 23

		X	

Section 23

Altitude at well \_\_\_\_\_

TYPE OF WELL: Drilled. Date Constructed 1/47

Depth drilled 287 ft. Depth cased 287 ft.

CASING RECORD:

10 inch std. pipe from 0 to 200 feet  
8 inch std. pipe from 150 to 287 feet

FINISH:

Perforations from 171 to 182 ft.; 199 to 206 ft.; 265 to 283 ft.

AQUIFERS:

WATER LEVEL:

36 feet below surface

PUMPING EQUIPMENT: Type Worthington 9 stage turbine H.P. 40

Capacity 500 G.P.M.

WELL TESTS:

Drawdown 61 ft. after \_\_\_\_\_ hours 750 G.P.M.

Drawdown 35 ft. after \_\_\_\_\_ hours 500 G.P.M.

USE OF WATER Industrial Temp. \_\_\_\_\_ °F. \_\_\_\_\_, 19 \_\_\_\_\_

SOURCE OF INFORMATION Well Registration Statement Cert. # GR-3796

DRILLER or DIGGER Force account

ADDITIONAL DATA:

Log X Water Level Measurements \_\_\_\_\_ Chemical Analysis \_\_\_\_\_ Aquifer Test \_\_\_\_\_

REMARKS:

