

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

STATE ENGINEER, SALEM, OREGON 97310

within 30 days from the date of well completion.

RECEIVED WATER WELL REPORT

DATE OF OREGON (Please type or print)

Do not write above this line

STATE ENGINEER SALEM, OREGON

MULT 001431

State Well No. 1N/3-356d

State Permit No.

(1) OWNER:

Name CITY OF WOOD VILLAGE
Address 2055 NE 238TH DR, TROUTDALE, ORE.

(2) TYPE OF WORK (check):

New Well Deepening Reconditioning Abandon
If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Driven
Cable Jetted
Dug Bored

(4) PROPOSED USE (check):

Domestic Industrial Municipal
Irrigation Test Well Other

CASING INSTALLED:

Threaded Welded
12" Diam. from 0 ft. to 458 ft. Gage 330
" Diam. from ft. to ft. Gage
" Diam. from ft. to ft. Gage

PERFORATIONS:

Perforated? Yes No
Type of perforator used STAR
Size of perforations 3/8 in. by 1/4 in.
400 perforations from 439 ft. to 449 ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS:

Well screen installed? Yes No
Manufacturer's Name
Type Model No.
Diam. Slot size Set from ft. to ft.
Diam. Slot size Set from ft. to ft.

(8) WATER LEVEL: Completed well.

Static level 250 ft. below land surface Date 12/29/69
Artesian pressure lbs. per square inch Date

(9) WELL TESTS:

Drawdown is amount water level is lowered below static level
Was a pump test made? Yes No If yes, by whom? STRASSER
Yield: 313 gal./min. with 83 ft. drawdown after 24 hrs.
200 " 57 " 25 "
490 " 166 " 8 "
Bailer test gal./min. with ft. drawdown after hrs.
Artesian flow g.p.m. Date
Temperature of water 54° Was a chemical analysis made? Yes No

(10) CONSTRUCTION:

Well seal—Material used CEMENT GROUT
Depth of seal FROM SURFACE TO 61 ft.
Diameter of well bore to bottom of seal 16 in.
Were any loose strata cemented off? Yes No Depth
Was a drive shoe used? Yes No
Did any strata contain unusable water? Yes No
Type of water? depth of strata
Method of sealing strata off
Was well gravel packed? Yes No Size of gravel:
Gravel placed from ft. to ft.

(11) LOCATION OF WELL:

County MULT. Driller's well number 5231
SE 1/4 NW 1/4 Section 35 T. 1N. R. 3E. W.M.
Bearing and distance from section or subdivision corner

(12) WELL LOG:

Diameter of well below casing 12
Depth drilled 546 ft. Depth of completed well 458 ft.
Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level as drilling proceeds. Note drilling rates.

| MATERIAL | From | To | SWL |
|-----------------------|------|-----|-----|
| GRAVEL AND BOULDERS | 0 | 51 | |
| GRAVEL AND BROWN CLAY | 51 | 78 | |
| BROWN SAND AND CLAY | 78 | 128 | |
| GRAVEL AND CLAY | 128 | 146 | |
| CEMENTED GRAVEL | 146 | 258 | |
| GRAVEL, SOME BINDER | 258 | 270 | |
| CEMENTED GRAVEL | 270 | 279 | |
| LARGE GRAVEL | 279 | 291 | |
| CEMENTED GRAVEL | 291 | 438 | |
| BROWN SAND AND GRAVEL | 438 | 440 | |
| WATER BEARING GRAVEL | 440 | 450 | |
| GREY SHALE | 450 | 546 | |

Work started SEPT 18 1969 Completed FEB 2 1970
Date well drilling machine moved off of well FEB 3 1970

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Donald Johnson Date FEB 4, 1970
(Drilling Machine Operator)

Drilling Machine Operator's License No. 56

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME R. L. STRASSER DRILLING CO
(Person, firm or corporation) (Type or print)

Address 8110 SE SUNSET LANE PORTLAND ORE

[Signed] Robert L. Strasser
(Water Well Contractor)

Contractor's License No. 10 Date FEB 4, 1970