

WATER WELL REPORT
STATE OF OREGON

MULT
001510

RECEIVED

State Well No. 11/55-28

FEB 29 1984

State Permit No.

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER:

Name DR. MONICA A. YOSHINAGA
Address 44445 NE ALEX BARR RD
City CORBETT State OR

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐
Thermal: ☐ Withdrawal ☐ Reinjection ☐

(5) CASING INSTALLED:

Steel ☒ Plastic ☐
Threaded ☐ Welded ☒

6" Diam. from 1 ft. to 43 ft. Gauge .250

" Diam. from ft. to ft. Gauge

LINER INSTALLED:

4" Diam. from 5 ft. to 385 ft. Gauge 200#

(6) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used SAW

Size of perforations 1/8 in. by 5 in.

115 perforations from 300 ft. to 380 ft.

perforations from ft. to ft.

perforations from ft. to ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name

Type Model No.

Diam. Slot Size Set from ft. to ft.

Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS:

Drawdown is amount water level is lowered below static level

Is a pump test made? ☐ Yes ☒ No If yes, by whom?

Field: gal./min. with ft. drawdown after hrs.

" " " " "

Air test 6 gal./min. with drill stem at 380 ft. 4 hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION:

Special standards: Yes ☐ No ☒

Well seal—Material used CEMENT

Well sealed from land surface to 47 ft.

Diameter of well bore to bottom of seal 10+ in.

Diameter of well bore below seal 6 in.

Number of sacks of cement used in well seal 28 sacks

How was cement grout placed? PUMP

Was pump installed? NO Type HP Depth ft.

Was a drive shoe used? ☐ Yes ☒ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☐ Yes ☒ No Size of gravel: ft.

Gravel placed from ft. to ft.

(10) LOCATION OF WELL:

County MULT. Driller's well number

1/4 1/4 Section 28 T. 1N. R. 5E. W.M.

Tax Lot # 27 Lot Blk Subdivision

Address at well location: SAME

(11) WATER LEVEL: Completed well.

Depth at which water was first found 370 ft.

Static level 268 ft. below land surface. Date 2/3/84

Artesian pressure lbs. per square inch. Date

(12) WELL LOG:

Diameter of well below casing

Depth drilled ft. Depth of completed well ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
CLAY, BOULDERS AND GRAVEL	0	32	
SOFT BASALT ROCK	32	37	
BASALT ROCK HARD w/ SOME FRACTURES	37	355	
BASALT ROCK HARD w/ LARGE FRACTURES	355	385	268

Work started JAN. 22 1984 Completed FEB. 4 1984

Date well drilling machine moved off of well FEB. 4 1984

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Daniel V. W. [Signature] Date FEB. 6, 1985

(Drilling Machine Operator)

Drilling Machine Operator's License No.

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

Name D. V. WILKINS & CO. INC.

(Person, firm or corporation)

(Type or print)

Address 16150 SE. NORMA MILWAUKEE, OR

[Signed] Daniel V. W. [Signature]

(Water Well Contractor)

Contractor's License No. 554 Date FEB. 6, 1984

NOTICE TO WATER WELL CONTRACTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*12658-690