

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED

FEB 12 1986

PLEASE TYPE or PRINT IN INK

MULT

001519

1N/5E-31

(for official use only)

WATER RESOURCES DEPT

(1) OWNER: SALEM, OREGON

Name CLARK KLOCK
Address RT 2 BOX 800
City Corbett State ORE

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary Air ☒ Driven ☐
Rotary Mud ☐ Dug ☐
Cable ☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☐ Industrial ☐ Municipal ☐
Thermal: ☒ Withdrawal ☐ Reinjection ☐
Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(5) CASING INSTALLED: Steel ☒ Plastic ☐

Threaded ☐ Welded ☒
6" Diam. from +1 ft. to 19 ft. Gauge 2.50

LINER INSTALLED: Steel ☐ Plastic ☒

Threaded ☐ Welded ☒
4" PVC Diam. from 0 ft. to 130 ft. Gauge 00016

(6) PERFORATIONS: Perforated? ☒ Yes ☐ No

Size of perforations 1/16 in. by 6 in.
480 perforations from 0 ft. to 130 ft.
perforations from ft. to ft.
perforations from ft. to ft.

(7) SCREENS: Well screen installed? ☐ Yes ☐ No

Manufacturer's Name Model No.
Type Diam. Slot Size Set from ft. to ft.
Diam. Slot Size Set from ft. to ft.

(8) WELL TESTS: Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Ted
Pump: 8 gal./min. with 8.5 ft. drawdown after 9 hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test gal./min. with ft. drawdown after hrs.

Artesian flow g.p.m.

Temperature of water Depth artesian flow encountered ft.

(9) CONSTRUCTION: Special standards: Yes ☐ No ☒

Well seal—Material used Cement
Well sealed from land surface to 19 FT ft.

Diameter of well bore to bottom of seal 10 in.

Diameter of well bore below seal 10-6 in. 10" 40 FT 6" 40-150

Amount of sealing material 10 sacks ☒ pounds ☐

How was cement grout placed? Poured Through
Trimmy Pipe

Was pump installed? Type HP Depth ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs Size: location ft.

Did any strata contain unusable water? ☐ Yes ☐ No

Type of Water? depth of strata

Method of sealing strata off

Was well gravel packed? ☒ Yes ☐ No Size of gravel: 3/8" 27

Gravel placed from 19 ft. to 150 ft.

(10) LOCATION OF WELL by legal description:

County Mult 1/4 1/4 of Section 31 of
Township 1N Range 5E WM.
(Township is North or South) (Range is East or West)

Tax Lot Lot Block Subdivision

MAILING ADDRESS OF WELL (or nearest address)

(11) WATER LEVEL OF COMPLETED WELL:

Depth at which water was first found 2.5 ft.

Static level 15 ft. below land surface. Date 12-20-85

Artesian pressure lbs. per square inch. Date

(12) WELL LOG: Diameter of well below casing 10-6

Depth drilled 150 ft. Depth of completed well 130 ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	0	1	
Red Clay	1	25	
CLAY STONE + SAND	25	35	
CLAY	35	80	
CLAY + Shell Brown	80	100	
CLAY	100	130	
Shell	130	140	
Hard BASALTS Rock	140	150	
(Fractured)			
VOID Took water	135	150	
Filled in	130-150		
PEA GRAVEL,			
SAND, CEMENT.			

Date work started 12-19-85 /completed 1-3-86

Date well drilling machine moved off of well 1-3 19 86

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Date , 19

(bonded) Water Well Constructor Certification:

Bond 2546611 Issued by: SAFE CO
(number) (Surety Company Name)

On behalf of Ted Pulliam well drilling
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

(Signed) Ted Pulliam
(Water Well Constructor)

(Dated) 1-6-86

NOTICE TO WATER WELL CONSTRUCTOR

The original and first copy of this report are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date of well completion.

SP*46866-690