

STATE ENGINEER
Salem, Oregon

MULT Well Record
001853

STATE WELL NO. 2N/1W-36E
COUNTY Multnomah
APPLICATION NO. GR-4164

OWNER: Bonneville Power Administration

MAILING ADDRESS: P.O. Box 3537

LOCATION OF WELL: Owner's No.

CITY AND STATE: Portland 8, Oregon

SW 1/4 NW 1/4 Sec. 36 T. 2 N. E. R. 1 W., W.M.

Bearing and distance from section or subdivision
corner N. 87° 42' 23" E. 397.3 ft. from E. SE Cor. of
Wm. Catton DIC 43

X			

Section 36

Altitude at well

TYPE OF WELL: Drilled Date Constructed 2/40

Depth drilled 108 ft. Depth cased 108 ft.

CASING RECORD:

10 inch standard pipe from surface to 108 feet

FINISH:

AQUIFERS:

WATER LEVEL:

36 feet below surface

PUMPING EQUIPMENT: Type Peerless 8"xA 9 stage H.P. 15
Capacity 125 G.P.M.

WELL TESTS:

Drawdown 2 ft. after 250 hours G.P.M.
Drawdown ft. after hours G.P.M.

USE OF WATER Domestic Temp. °F. 19

SOURCE OF INFORMATION Well Registration Statement Cert. # GR-3729

DRILLER or DIGGER R. J. Strasser Drilling Company

ADDITIONAL DATA:

Log X Water Level Measurements Chemical Analysis Aquifer Test

REMARKS: Log	Thickness	Depth to Bottom
Sand clay	6	6
Sand	72	78
Gravel & boulders	4	82
Sand gravel (water bearing)	19	101
Sand gravel & boulders	7	108