

RECEIVED MULT
002377
JUL 16 1962

WATER WELL REPORT
STATE OF OREGON

State Well No. 113-23400
State Permit No. G-2344

File Original and
First Copy with the
STATE ENGINEER,
SALEM, OREGON

(1) OWNER:

Name Cletus J. Rupp
Address Rt. 3, Box 271
Gresham, Oregon

(2) LOCATION OF WELL:

County Multnomah Owner's number, if any—
1/4 1/4 Section 23 T. 1 R. 3 E. W.M.
Bearing and distance from section or subdivision corner

(3) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐
If abandonment, describe material and procedure in Item 11.

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☒ Test Well ☐ Other ☐

(5) TYPE OF WELL:

Rotary ☐ Driven ☐
Cable ☒ Jetted ☐
Dug ☐ Bored ☐

(6) CASING INSTALLED:

Threaded ☐ Welded ☒
6 " Diam. from 0 ft. to 237.6 ft. Gage 280
5 " Diam. from 234 ft. to 271 ft. Gage 250
" Diam. from _____ ft. to _____ ft. Gage _____

(7) PERFORATIONS:

Perforated? ☒ Yes ☐ No

Type of perforator used Torch

SIZE of perforations 3/16 in. by 3 in.
132 perforations from 237 ft. to 270 ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

(8) SCREENS:

Well screen installed ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
" Slot size _____ Set from _____ ft. to _____ ft.

(9) CONSTRUCTION:

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____
Gravel placed from _____ ft. to _____ ft.
Was a surface seal provided? ☒ Yes ☐ No To what depth? 70 ft.
Material used in seal— Cement
Did any strata contain unusable water? ☐ Yes ☒ No
Type of water? _____ Depth of strata _____
Method of sealing strata off _____

(10) WATER LEVELS:

Static level 168 ft. below land surface Date 7-5-62
Artesian pressure _____ lbs. per square inch Date _____

Log Accepted by:

[Signed] Cletus Rupp Date 7-12, 1962
(Owner)

(11) WELL TESTS:

Drawdown is amount water level is lowered below static level

Was a pump test made? ☒ Yes ☐ No If yes, by whom? Driller
Yield: 160 gal./min. with 32 ft. drawdown after 4 hrs.

" " " "
" " " "

Bailer test gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow g.p.m. Date _____

Temperature of water 52 Was a chemical analysis made? ☐ Yes ☒ No

(12) WELL LOG:

Diameter of well 6 inches.

Depth drilled 272 ft. Depth of completed well 272 ft.

Formation: Describe by color, character, size of material and structure, and show thickness of aquifers and the kind and nature of the material in each stratum penetrated, with at least one entry for each change of formation.

MATERIAL	FROM	TO
Yellow clay	0	50
Red clay	50	65
Soft rock	65	67
Firm rock, gray	67	80
Soft pink rock	80	81
Hard rock, gray	81	132
Red rock	132	142
decomposed cinders	142	152
Gravel, sand with black binder	152	176
Gravel, clay	176	193
Blue-gray sand rock, gravel streaks	193	230
(Water 30 gal. per minute)	132	230
Gravel & clay, brown	230	234
Brown clay	234	237
Sand	237	238
Gravel	238	247
Gravel, water bearing	247	253
Gravel, water bearing	253	272

Work started 6-5 19 62 Completed 7-5 1962

(13) PUMP:

Manufacturer's Name _____
Type: _____ H.P. _____

Well Driller's Statement:

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.

NAME Calvin C. Bram
(Person, firm, or corporation) (Type or print)

Address 17120 S. E. Foster Rd.

Driller's well number _____

[Signed] Calvin C. Bram
(Well Driller)

License No. 222 Date 7-12, 1962