

STATE ENGINEER
Salem, Oregon

MULT Well Record

STATE WELL NO. 1/4-18M
COUNTY MULTNOMAH
APPLICATION NO. GR-2822

OWNER: Harry W. Park,

MAILING ADDRESS: Rt. 2, Box 829

LOCATION OF WELL: Owner's No.

CITY AND STATE: Gresham, Oregon

NW 1/4 SW 1/4 Sec. 19 T. 1 N. S., R. 4 E. W., W.M.

Bearing and distance from section or subdivision corner 1980' N. and 660' E.

Section

Altitude at well

TYPE OF WELL: drilled Date Constructed 1951

Depth drilled 197 Depth cased 197

CASING RECORD:

10-inch

FINISH:

10-inch pipe perforated 1/2" x 1 1/2" from 140 to 160
10-inch pipe perforated 1/2" x 1 1/2" from 189 to 196

AQUIFERS:

Clay, gravel

WATER LEVEL:

120-feet

PUMPING EQUIPMENT: Type Fairbanks Morse Turbine H.P. 25

Capacity 275 G.P.M.

WELL TESTS:

Drawdown 120 ft. after hours Pumping 250 G.P.M.

Drawdown 170 ft. after hours Pumping 325 G.P.M.

USE OF WATER irrigation Temp. °F. 19

SOURCE OF INFORMATION GR-2662

DRILLER or DIGGER A. M. Janssen Drilling Co., P. O. Box 76, Reedville, Oregon

ADDITIONAL DATA:

Log Water Level Measurements Chemical Analysis Aquifer Test

REMARKS:

Clay	0	71	71	71
Gravel	71	135	64	135
Water gravel	135	160	25	160
Cemented gravel	160	189	29	189
Water gravel	189	197	8	197