

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MULT
3163
SEP - 9 1992
WATER RESOURCES DEPT.
SALEM, OREGON

15/4E/16
45237
(START CARD) #

(1) OWNER:

Name Garison Nursery, Inc Well Number _____
Address 32627 SE Lusted Rd
City Gresham State OR Zip 97030

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD:

☒ Rotary Air ☐ Rotary Mud ☐ Cable
☐ Other

(4) PROPOSED USE:

☐ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval ☐ Yes ☒ No Depth of Completed Well 483'
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
14"	0	45	CEM.	0	45	25
10"	45	110	CEM.	100	110	70
8"	110	483				

How was seal placed: Method ☐ A ☐ B ☒ C ☐ D ☐ E
☐ Other

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

(6) CASING/LINER:

	Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing:	10"	+1 1/2'	110'	250	☒	☐	☒	☐
	8"	0	483'	250	☒	☐	☒	☐
Liner:					☐	☐	☐	☐

Final location of shoe(s) 10' @ 110' 8' @ 483' ODEX

(7) PERFORATIONS/SCREENS:

☒ Perforations Method AIR PERF.
☐ Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
400	460	1/4" x 1/8"	950			☒	☐
						☐	☐
						☐	☐
						☐	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
350		460	1 hr.

Temperature of Water 54° Depth Artesian Flow Found _____

Was a water analysis done? ☐ Yes By whom _____

Did any strata contain water not suitable for intended use? ☐ Too little

☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other

Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County MULT Latitude _____ Longitude _____
Township 13N N or S. Range 4E E or W. WM. _____
Section 16 1/4 _____ 1/4 _____
Tax Lot _____ Lot _____ Block _____ Subdivision _____

Street Address of Well (or nearest address) Lusted Rd Gresham 32627 SE

(10) STATIC WATER LEVEL:

200 ft. below land surface. Date 8-14-92

Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 32

From	To	Estimated Flow Rate	SWL
32	95	60	10
392	470	350	200

(12) WELL LOG:

Ground elevation _____

Material	From	To	SWL
SOIL	0	8	
CLAY BRN.	8	32	
GRAVEL MED. MULTI-COLORED	32	95	10
CEMENTED GRAVEL BRN. HARD	95	147	
GRAVEL MED MULTI-COLORED	147	260	
CEMENTED GRAVEL BLACK MED	260	382	
CEMENTED GRAVEL BRN.	382	412	
CEMENTED GRAVEL BLACK	412	470	200
CLAY BRN.	470	483	
* Cement placed 110 to 120 FT. 10 sacks.			
Recommend pump setting			
480 FT or not more			
than 500 GPM.			

Date started 7-25-92 Completed 8-15-92

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed DeW. Rutter WWC Number 016
Date 8-24-92

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed DeW. Rutter WWC Number 016
Date 8-24-92