

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MULT 3689 SEP 17 1993
WATER RESOURCES DEPT.
SALEM, OREGON

(START CARD) # 38308

(1) OWNER: Well Number: 03
Name: KENNETH KERSLAKE
Address: 1605 SE 302
City: Troutdale State: OR Zip: 97060

(2) TYPE OF WORK:

☒ New Well ☐ Deepen ☐ Recondition ☐ Abandon

(3) DRILL METHOD

☐ Rotary Air ☐ Rotary Mud ☒ Cable
☐ Other

(4) PROPOSED USE:

☒ Domestic ☐ Community ☐ Industrial ☒ Irrigation
☐ Thermal ☐ Injection ☐ Other

(5) BORE HOLE CONSTRUCTION:

Special Construction approval Yes No Depth of Completed Well: 240 ft.
Explosives used Yes No Type Amount

HOLE			SEAL			Amount sacks or pounds
Diameter	From	To	Material	From	To	
12	0	20	Cement	0	20	17
10	20	100	Cement	20	100	21
8	100	240	Open			

How was seal placed: Method ☒ A ☐ B ☐ C ☐ D ☐ E
☐ Other

Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8	1	240	250	☒	☐	☐	☐
Liner:				☐	☐	☐	☐

Final location of sheets:

(7) PERFORATIONS/SCREENS:

☒ Perforations Method: Drill Down Perf.
☐ Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
195	240	1/4"	520	8		☒	☐

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☒ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
1.5	0		4 hr.

Temperature of water: 52 Depth Artesian Flow Found

Was a water analysis done? ☐ Yes By whom

Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other: NO

Depth of strata:

(9) LOCATION OF WELL by legal description:

County: MULTNOMAH Latitude Longitude
Township: 1 N S. Range: 4 E or W, WM.
Section: 34 1/4 Block Subdivision
Tax Lot Lot Block Subdivision
Street Address of Well (or nearest address): CORBETT, OR, 97019

(10) STATIC WATER LEVEL:

195 ft. below land surface. Date: 8/18/93
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:

Depth at which water was first found: 195

From	To	Estimated Flow Rate	SWL
195	240	15	195

(12) WELL LOG:

Material	From	To	SWL
Top Soil	0	1	
Clay Brown w/ Sand	1	27	
Centrifuged Gravel	27	83	
Sand STONE	83	195	
Gravel + Small Boulders w/ 3	195	290	195

Date started: 6/10/93 Completed: 8/23/93

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed: WWC Number: Date:

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.

Signed: WWC Number: 1328 Date: 9/10/93