

FEB 11 1994

WATER RESOURCES DEPT.
SALEM, OREGONPORT OF PORTLAND
ECONOMY PARKING LOT IRRIGATION WELL

Start Card No. 56029

By Schneider Drilling Co.

<u>Depth</u>		
<u>From</u>	<u>To</u>	
0	21	Sand, brown, fine-med
21	30	Sand, brown & blue, fine
30	35	Clay, blue-green, fine, sandy
35	45	Clay, blue, gray & brown layered, fine, sandy
45	130	Sand, gray, fine-med
130	137	Sand, med-fine, w/wood, gray
137	150	Sand, gray, med-fine, w/wood, trace of small gravel
150	166	Sand, gray, med, w/some small gravel
166	171	Boulder
171	173	Gravel, 1"-, & sand, med-coarse, w/some cemented
173	180	Gravel, 3"-, & sand, blk, med-crse, some cemented, some cly, grn
180	183	Gravel, 3"-, & sand, med-coarse
183	192	Gravel, 3"-, & sand, med-coarse, some cemented
192	194	Gravel, 4"-, w/clay, blue-gray
194	195	Gravel, 4"-, & sand, med-crse, w/clay, blue-gray
195	200	Gravel, 4"-, w/clay, blue-gray
200	204	Gravel, 2"-, & sand, med-coarse
204	210	Gravel, 4"-, & sand, med-coarse, w/some clay, blue-gray
210	215	Clay, blue-green, sticky
215	220	Clay, blue-green, gritty

30

MULT 4017

Pumping Level
(Feet below ground)

RECEIVED

FEB 11 1994

WATER RESOURCES DEPT.
SALEM, OREGON

SWL

10

Time in Minutes

100

Port of Portland - Economy lot Well
1000 gpm Well Test
11/2/94
by Schneider Drilling Co.

50

