

REC

AUG 21 1995

MULT
4932

015/048/17

State of Oregon

WATER WELL REPORT (as required by ORS 537.765) Page 1 of 1

Start Card # 49931

SALEM, OREGON

(1) OWNER:
Name EKSTROM NURSERY
Address 1600 SE 282ND
City GRESHAM St OR Zip 97080

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 480 ft
Explosives used NO Type Amount

HOLE				SEAL		
Diam.	From	To	Material	From	To	Amount
14	0	160	CEMENT	0	160	58 SACKS
10	160	260	CEMENT	200	260	24 SACKS
9 5/8	260	480				

Seal placement method C

Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	10	+1	220	.250	STEEL	WELDED
	8	+2	480	.250	STEEL	WELDED

Liner

Final Location of shoe(s) 10"-220' 8"-480' TUBEX

(7) PERFORATIONS/SCREENS:

☒ Perf. Method AIRKNIFE☐ Screens Type

Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
420	480	1/8X2	800			CASING

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
400		480	1 hr.
400		480	4HR

Temperature of water 53F Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL by legal description:

County MULT Lat. ° ' " Long. ° ' "
Township 1 S Range 4 E WM.
Section 17 1/4 1/4
Tax Lot 20 Lot Block Subdivision
Street Address of Well (or nearest Address)
6250 SE 302ND AVE GRESHAM, OR

(10) STATIC WATER LEVEL:

188 ft. below land surface. Date 07/31/95
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 160

From	To	Est Flow Rate	SWL
160	210	30-50 GPM	160
300	480	400+ GPM	188

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
BROWN CLAY	2	39	
BROWN CLAY & GRAVEL	39	61	
CEMENTED GRAVEL	61	160	
LOOSE GRAVEL	160	210	160
LIGHTLY CEMENTED GRAVEL	210	230	
BLUE CLAY & GRAVEL	230	250	
CEMENTED GRAVEL	250	480	188

Date started 07/17/95

Completed 07/31/95

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Red W Pulliam* WWC Number 616
Date 08/01/95