

MULT
50011

DEC - 8 1995

State of Oregon

WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

Start Card # 74620

(1) OWNER: Well No. 11091995
 Name EKSTROM NURSERY
 Address 1600 SE 282ND
 City GRESHAM St OR Zip 97080

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMEST/IRRIGAT

(5) BORE HOLE CONSTRUCTION:
 Special Construction Approval NO _____ Depth of Compl. Well 480 ft
 Explosives used NO _____ Type _____ Amount _____
 HOLE SEAL

Diam.	From	To	Material	From	To	Amount
14	0	120	CEMENT	0	120	79 SACKS
10	120	220	CEMENT	180	220	36 SACKS
9 1/2	220	480				

Seal placement method C
 Backfill: from _____ ft to _____ ft Material _____
 Gravel: from _____ ft to _____ ft Size _____

(6) CASING/LINER:

Casing	Diam.	From	To	Gauge	Material	Connection
	10	+1	200	.250	STEEL	WELDED
	8	0	480	.250	STEEL	WELDED

 Liner _____
 Final Location of shoe(s) 10"-200' 8 1/2"-480' TBX

(7) PERFORATIONS/SCREENS:
 Perf. Method AIRKNIFE
 Screens Type _____ Material _____

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
420	480	1/8X2	1200			CASING

(8) WELL TESTS: Minimum testing time is 1 hour
 Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
300		480	1 hr.
300		480	4 HR

 Temperature of water 52F Depth Artesian Flow Found _____
 Was water analysis done? NO By whom _____
 Reason for water not suitable for use _____
 Depth of strata _____

SALEM, OREGON
 (9) LOCATION OF WELL by legal description:
 County MULT Lat. ° ' " Long. ° ' "
 Township 1 S Range 4 E WM.
 Section 18 SW 1/4 SE 1/4
 Tax Lot 110 Lot Block Subdivision
 Street Address of Well (or nearest Address)
 W OF 29840 SE CHASE ROAD GRESHAM, OR 97080

(10) STATIC WATER LEVEL:
 149 ft. below land surface. Date 11/07/95
 Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
 Depth at which water was first found 220

From	To	Est Flow Rate	SWL
220	480	300+	149

(12) WELL LOG:

Material	From	To	SWL
TOP SOIL	0	2	
BROWN CLAY	2	70	
CLAY & GRAVEL	70	90	
LIGHTLY CEMENTED GRAVEL	90	480	149

 Date started 10/12/95 Completed 11/07/95

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.
 Signed _____ WWC Number _____
 Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.
 Signed *Red W Pulliam* WWC Number 616
 Date 11/09/95