

MULT 50705

State of Oregon

WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

Start Card # 74623

(1) OWNER: Well No. 12271995
 Name TIM FISHER
 Address 28810 SE WHEELER ROAD
 City BORING St OR Zip 97009

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 500 ft
 Explosives used NO Type Amount

HOLE				SEAL		
Diam.	From	To	Material	From	To	Amount
14	0	40	BENTONITE	0	20	1500 LBS
12	40	95	CEMENT	20	95	110 SACKS
10	95	220	CEMENT	180	220	70 SACKS
9 5/8	220	500				

Seal placement method C

Backfill: from ___ ft to ___ ft Material

Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	10	+1	180	.250	STEEL	WELDED
	8	0	500	.250	STEEL	WELDED

Liner

Final Location of shoe(s) 10-180' 7 1/2" TUBEX-500'

(7) PERFORATIONS/SCREENS:

[X] Perf. Method AIRKNIFE

[_] Screens Type Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
460	500	1/8X2	1200			CASING

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
400		460	1 hr.
400		460	2 HR

Temperature of water 51F Depth Artesian Flow Found

Was water analysis done? NO By whom

Reason for water not suitable for use

Depth of strata

(9) LOCATION OF WELL by legal description:

County MULT Lat. ° ' " Long. ° ' "
 Township 1 S Range 3 E WM.
 Section 24 SE 1/4 SE 1/4
 Tax Lot 2200 Lot Block Subdivision
 Street Address of Well (or nearest Address)
 NE CORNER SE 282ND&STONE ROAD BORING, OR 97009

(10) STATIC WATER LEVEL:

78 ft. below land surface. Date 12/26/95
 Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 18

From	To	Est Flow Rate	SWL
18	30	10-20 GPM	18
135	170	50+ GPM	50
280	500	400+ GPM	78

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
BROWN CLAY	2	8	
LOOSE GRAVEL & BOULDERS	8	35	18
LIGHTLY CEMENTED GRAVEL & BOULDERS	35	95	
LOOSE GRAVEL & BOULDERS	95	170	50
LIGHTLY CEMENTED GRAVEL & SAND	170	280	
FINE CEMENTED SAND & GRAVEL	280	420	78
COARSE CEMENTED SAND & GRAVEL	420	500	78

Date started 12/05/95

Completed 12/26/95

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
 Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *[Signature]* WWC Number 616
 Date 12/27/95