

MULT
51631

Well # L07361

(1) OWNER: Well No. L07361
Name EKSTROM NURSERY
Address 1600 SE 282ND
City GRESHAM St OR Zip 97080

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO		Depth of Compl. Well		500 ft		
Explosives used NO	Type	Amount				
HOLE		SEAL				
Diam.	From	To	Material	From	To	Amount
14	0	80	CEMENT	0	80	41 SACKS
10	80	190	CEMENT	150	190	49 SACKS
9 5/8	190	500				

Seal placement method C

Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	10	+1	160	.250	STEEL	WELDED
	8	0	500	.250	STEEL	WELDED

Liner

Final Location of shoe(s) 10"-160' 7 1/2" TUBEX-500'

(7) PERFORATIONS/SCREENS:

Perf. Method AIRKNIFE

Screens Type _____ Material _____

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner
480	500	1/8X2	1200			CASING

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
150		490	1 hr.
150		490	2HR

Temperature of water 52F Depth Artesian Flow Found _____

Was water analysis done? NO By whom _____

Reason for water not suitable for use _____

Depth of strata _____

(9) LOCATION OF WELL by legal description:

County MULT Lat. ° ' " Long. ° ' "
Township 1 S Range 4 E WM.
Section 12 NW 1/4 SW 1/4
Tax Lot Lot Block Subdivision
Street Address of Well (or nearest Address)
7722 SE 282ND BORING, OR 97009

(10) STATIC WATER LEVEL:

137 ft. below land surface. Date 07/16/96
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 140		Est Flow Rate	SWL
From	To		
140	150	50 GPM	80
360	500	150 GPM	137

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	3	
BROWN CLAY	3	49	
CLAY & GRAVEL	49	57	
LIGHTLY CEMENTED GRAVEL & BOULDERS	57	120	
LIGHTLY CEMENTED GRAVEL	120	290	90
LIGHTLY CEMENTED GRAVEL & BOULDER	290	360	
LIGHTLY CEMENTED GRAVEL	360	440	137
LIGHTLY CEMENTED SAND & GRAVEL	440	460	137
LIGHTLY CEMENTED GRAVEL	460	500	137

RECEIVED

AUG 19 1996

WATER RESOURCES DEPT.
SALEM, OREGON

Date started 06/27/96

Completed 07/16/96

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *[Signature]* WWC Number 616
Date 08/15/96