

# RECEIVED

JUL 7 - 1998

**STATE OF OREGON**  
**WATER SUPPLY WELL REPORT**  
(as required by ORS 537.765)

**WATER RESOURCES DEPT.**  
**SALEM, OREGON**

WELL I.D. # L23442  
START CARD # 110683

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number \_\_\_\_\_  
Name Scappoose Fire District  
Address P.O. Box 685  
City Scappoose State OR Zip 97056

(2) TYPE OF WORK  
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:  
☒ Rotary Air ☐ Rotary Mud ☐ Cable ☐ Auger  
☐ Other \_\_\_\_\_

(4) PROPOSED USE:  
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation  
☐ Thermal ☐ Injection ☐ Livestock ☐ Other \_\_\_\_\_

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval ☐ Yes ☒ No Depth of Completed Well 196 ft.  
Explosives used ☐ Yes ☒ No Type \_\_\_\_\_ Amount \_\_\_\_\_

| HOLE          |           |            | SEAL             |          |           | Sacks or pounds |
|---------------|-----------|------------|------------------|----------|-----------|-----------------|
| Diameter      | From      | To         | Material         | From     | To        |                 |
| <u>10 1/8</u> | <u>0</u>  | <u>19</u>  | <u>Bentonite</u> | <u>0</u> | <u>19</u> | <u>9</u>        |
| <u>6 3/8</u>  | <u>19</u> | <u>196</u> |                  |          |           |                 |

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E  
☒ Other Poured  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:  
Diameter From To Gauge Steel Plastic Welded Threaded  
Casing: 6 4 1/2" 196 250 ☒ ☐ ☒ ☐  
Liner: \_\_\_\_\_  
Final location of shoe(s) 196'

(7) PERFORATIONS/SCREENS:  
☐ Perforations Method \_\_\_\_\_  
☐ Screens Type \_\_\_\_\_ Material \_\_\_\_\_  
From To Slot size Number Diameter Tele/pipe size Casing Liner

(8) WELL TESTS: Minimum testing time is 1 hour  
☐ Pump ☐ Bailor ☒ Air ☐ Flowing  
Yield gal/min Drawdown Drill stem at Time  
20 \_\_\_\_\_ 183 1 hr.  
Temperature of water 54 Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done? ☐ Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use? ☐ Too little  
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County Multnomah Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 2 (N) or S Range 2 E or (W) WM.  
Section 12 SE. 1/4 SW. 1/4  
Tax Lot 1990 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) 19260 N.W. Cleckwood  
Portland, OR 97231

(10) STATIC WATER LEVEL:  
85 ft. below land surface. Date 6-23-98  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 183'

| From       | To         | Estimated Flow Rate | SWL       |
|------------|------------|---------------------|-----------|
| <u>188</u> | <u>197</u> | <u>20</u>           | <u>85</u> |
|            |            |                     |           |
|            |            |                     |           |
|            |            |                     |           |

(12) WELL LOG:  
Ground Elevation \_\_\_\_\_

| Material                       | From       | To         | SWL       |
|--------------------------------|------------|------------|-----------|
| <u>Brown Silty Clay</u>        | <u>0</u>   | <u>90</u>  |           |
| <u>Blue Silty Clay</u>         | <u>90</u>  | <u>112</u> |           |
| <u>Blue Clay</u>               | <u>112</u> | <u>126</u> |           |
| <u>Green Clay &amp; Gravel</u> | <u>126</u> | <u>134</u> |           |
| <u>Brown Silty Clay</u>        | <u>134</u> | <u>177</u> |           |
| <u>Sand &amp; Gravel</u>       | <u>177</u> | <u>188</u> |           |
| <u>Sand &amp; Gravel</u>       | <u>188</u> | <u>197</u> | <u>85</u> |

Date started 6-22-98 Completed 6-23-98  
(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number \_\_\_\_\_  
Signed \_\_\_\_\_ Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1679  
Signed Jan D. [Signature] Date 7-5-98