

MULT
56024

RECEIVED

JUL 16 1998

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

WATER RESOURCES DEPARTMENT
SALEM, OREGON

State Well ID L15836
Start Card # 099531

(1) OWNER: Well No. L15836
Name AL & MYRA LADER
Address 34747 LUSTED ROAD
City GRESHAM St OR Zip 97080

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMEST/IRRIGAT

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 630 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
14 0 140 CEMENT 0 140 56 SACKS
12 140 400 CEMENT 350 400 44 SACKS
9 5/8 400 630

Seal placement method C

Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

	Diam.	From	To	Gauge	Material	Connection
Casing	10	+1	400	.250	STEEL	WELDED
	8	+18"	630	.250	STEEL	WELDED

Liner

Final Location of shoe(s) 400'91/2"/630'71/2" TUBEX

(7) PERFORATIONS/SCREENS:

[X] Perf. Method AIRKNIFE

[] Screens Type Material
Slot
From To Size Number Diam. Size Casing/liner
440 560 1/8X2 4000 _____ CASING

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
20		560	1 hr.
30	12		4HR/PUMP

Temperature of water 51F Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County MULT Lat. ° ' " Long. ° ' "
Township 1 S Range 4 E WM.
Section 15 SE 1/4 SW 1/4
Tax Lot 38 Lot Block Subdivision
Street Address of Well (or nearest Address)
34747 SE LUSTED ROAD GRESHAM, OR 97080

(10) STATIC WATER LEVEL:
405 ft. below land surface. Date 07/11/98
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 420
From To Est Flow Rate SWL
420 605 30+ GPM 405

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
TOP SOIL	0	2	
RED CLAY	2	68	
LIGHTLY CEMENTED GRAVEL & BOULDERS	68	350	
LIGHTLY CEMENTED GRAVEL, SAND & BLUE CLAY	350	560	405
GRAVEL, SAND & BLUE CLAY	560	605	450
BLUE CLAY	605	630	

WATER PERMIT #G-13144

Date started 06/16/98 Completed 07/11/98

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *[Signature]* WWC Number 616
Date 07/13/98