

RECEIVED

SEP 15 1999

MULT
58958

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

State Well ID L27714
Start Card # 099565

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER: Well No. L27714
Name LEE R MATTHEWS
Address 32033 MALLEY ROAD
City GRESHAM St OR Zip 97080

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 500 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
14 0 90 CEMENT 0 90 55 SACKS
12 90 302 CEMENT 260 302 30 SACKS
9 1/2 302 500

Seal placement method C

Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

Casing	Diam.	From	To	Gauge	Material	Connection
10	+1	302	.250	STEEL	WELDED	
Liner	8	280	320	.250	STEEL	WELDED

Final Location of shoe(s) 302' 9 1/2" TUBEX

(7) PERFORATIONS/SCREENS:

[X] Perf. Method TORCH

[] Screens Type Material
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
420 480 1/4X9 600 LINER

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
600		480	1 hr.
600		480	2 hr

Temperature of water 51F Depth Artesian Flow Found
Was water analysis done? NO By whom
Reason for water not suitable for use
Depth of strata

(9) LOCATION OF WELL BY legal description:
County MULT Lat. ° ' " Long. ° ' "
Township 1 S Range 4 E WM.
Section 20 NE 1/4 SE 1/4
Tax Lot 43 Lot Block Subdivision
Street Address of Well (or nearest Address)
7536 SE PLEASANT HOME ROAD GRESHAM, OR 97080

(10) STATIC WATER LEVEL:
231 ft. below land surface. Date 09/09/99
Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 45
From To Est Flow Rate SWL
45 50 10+ GPM 35
420 490 600+ GPM 231

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 2
RED CLAY 2 8
BROWN CLAY 8 72
CEMENTED GRAVEL & BOULDERS 72 240
BROWN CEMENTED GRAVEL WITH CLAY 240 345
BROWN CLAY & GRAVEL 345 420
BLACK CEMENTED GRAVEL 420 490 231
BLUE CLAY 490 500

Date started 08/21/99

Completed 09/09/99

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Ted D. Williams* WWC Number 616
Date 09/09/99