

MULT 60074

RECEIVED

FEB 10 2000

**WATER RESOURCES DEPT.
SALEM, OREGON**

**City of Portland
Sellwood Park Well
by Schneider Drilling Co.
SC# 118747 - Label #L33781**

FM	TO	DESCRIPTION
0	2	Top soil
2	11	Clay, brown, silty
11	14	Sand, brown, medium
14	19	Cobbles, gravel and clay, brown, sandy
19	31	Cobbles, gravel and sand, medium-coarse
31	36	Sand, medium-coarse
36	60	Gravel, 2" minus and sand, med-coarse
60	61	Clay, brown, medium
61	80	Lava rock, brown and grey, medium-hard, fractured
80	85	Lava rock, grey, hard
85	87	Lava rock, black, medium-hard, fractured
87	92	Lava rock, black, medium, fractured w/claystone
92	100	Lava rock, brown and grey, medium-hard, fractured
100	102	Lava rock, brown, soft, broken, vesicular w/some clay, brown
102	105	Lava rock, grey and brown, medium-hard, fractured
105	107	Lava rock, brown, soft broken w/ some clay, brown
107	110	Lava rock, grey and brown, medium-hard, fractured
110	112	Lava rock, brown and yellow, soft, broken
112	119	Lava rock, grey and brown, medium-hard, fractured, some vesicular
119	121	Lava rock, grey and brown, medium-hard fractured
121	128	Lava rock, grey and brown, hard, fractured
128	133	Clay, red, soft
133	135	Clay, grey, medium soft
135	160	Lava rock, grey, soft, well fractured, some vesicular w/some clay, green
160	185	Lava rock, grey and brown, medium-soft, fractured w/some clay, brown
185	218	Lava rock, grey, medium, well fractured
218	222	Lava rock, grey and brown, medium-soft, broken, vesicular
222	226	Clay, brown and green, medium-soft
226	230	Lava rock, brown and grey, medium-soft, broken, vesicular
230	300	Lava rock, grey and brown, hard, fractured
300	335	Lava rock, grey, medium-hard, fractured, some vesicular
335	341	Lava rock, black, medium, fractured, vesicular
341	389	Lava rock, black, medium-hard, fractured
389	390	Lava rock, black, medium-soft, fractured, vesicular, w/some clay, green
390	399	Lava rock, black and red, soft, broken, vesicular

RECEIVED

FEB 1 0 2000

**WATER RESOURCES DEPT.
SALEM, OREGON**

399	404	Lava rock, black, medium-hard, fractured
404	409	Lava rock, grey, hard, vesicular & some claystone
409	424	Lava rock, black, hard w/some claystone, multi-colored
424	426	Lava rock, black, hard, fractured w/some claystone, multi-colored
426	453	Lava rock, grey, fractured
453	461	Lava rock, grey w/some red, fractured
461	462	Lava rock, black w/some red, some fractures & vesicles
462	464	Lava rock, black, fractured, some vesicular
464	469	Lava rock, black, lots of vesicular, some fractures
469	470	Lava rock, black, very fractured
470	472	Lava rock, black-grey, some vesicular & some claystone, brown & green
472	485	Claystone, multi-colored & clay, grey
485	491	Lava rock, black, vesicular
491	503	Lava rock, grey, hard
503	510	Lava rock, black, medium, fractured, some vesicles
510	520	Lava rock, grey, hard, some fractures
520	529	Lava rock, grey, hard, fractured w/ brown & green claystone
529	541	Lava rock, grey, hard some fractures
541	548	Lava rock, grey-red, medium w/ green claystone
548	550	Clay, red, medium
550	553	Claystone, multi-colored, hard
553	560	Claystone, green, hard

RECEIVED

FEB 10 2000

WATER RESOURCES DEPT.
SALEM, OREGON

**Portland Sellwood Park Well Test
1/25/00 @ 300 gpm**

