

(1) OWNER: Well No. L44587
Name VILLAGE RETIREMENT CENTER
Address 4501 W POWELL BLVD
City GRESHAM St OR Zip 97080

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO _____ Depth of Compl. Well 320 ft
Explosives used NO _____ Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
14 0 60 BENTONITE 0 10 18 SACKS
10 60 180 CEMENT 10 60 25 SACKS
8 180 280 CEMENT 140 180 58 SACKS
5 1/2 280 320
Seal placement method C & POURED IN
Backfill: from _____ ft to _____ ft Material _____
Gravel: from _____ ft to _____ ft Size _____

(6) CASING/LINER:
Casing Diam. From To Gauge Material Connection
8 +1 180 .250 STEEL WELDED
Liner 6 100 280 .250 STEEL WELDED

Final Location of shoe(s) 5 1/2" TUBEX 280'

(7) PERFORATIONS/SCREENS:
[] Perf. Method _____
[] Screens Type _____ Material _____
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
150 _____ 280 1 hr.
150 _____ 280 2 hr.
Temperature of water 51F Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use _____
Depth of strata _____

(9) LOCATION OF WELL by legal description:
County MULT Lat. ° ' " Long. ° ' "
Township 1 S Range 3 E WM.
Section 7 SE 1/4 SE 1/4
Tax Lot 900 Lot Block Subdivision
Street Address of Well (or nearest Address)
4501 W POWELL BLVD GRESHAM, OR 97080

(10) STATIC WATER LEVEL:
69 ft. below land surface. Date 5-16-01
Artesian pressure _____ lb per square in. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 30
From To Est Flow Rate SWL
30 35 5-10 GPM 33
100 120 10-20 GPM 51
280 320 150 GPM 69

(12) WELL LOG:
Material Ground elevation From To SWL
TOP SOIL 0 2
BROWN CLAY & GRAVEL 2 40 33
LIGHTLY CEMENTED GRAVEL & BOULDERS 40 140 51
LIGHTLY CEMENTED GRAVEL & BOULDERS WITH SEAMS OF BLUE CLAY 140 280
LIGHTLY CEMENTED GRAVEL & BOULDERS 280 320 69
RECEIVED
JUN 18 2001
WATER RESOURCES DEPT
SALEM, OREGON
Date started 5-7-01 Completed 5-16-01

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Lee M. Sullivan* WWC Number 616
Date 06/15/01