

(1) OWNER: Well No. L52971
Name ALBERT GARRE
Address 12532 NE ROSE PARKWAY
City PORTLAND St OR Zip 97230

(9) LOCATION OF WELL by legal description:
County MULT Lat. ° ' " Long. ° ' "
Township 1 N Range 2 E WM.
Section 23 SE 1/4 SW 1/4
Tax Lot 1700 Lot Block Subdivision
Street Address of Well (or nearest Address)
12700 NE SHAVER STREET PORTLAND, OR 97230

RECEIVED

JUN 25 2002

WATER RESOURCES DEPT.
SALEM, OREGON

(2) TYPE OF WORK: NEW WELL
(3) DRILL METHOD: ROTARY AIR
(4) PROPOSED USE: IRRIGATION

(10) STATIC WATER LEVEL:
80 ft. below land surface. Date 06/19/02
Artesian pressure _____ lb per square in. Date _____

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 245 ft
Explosives used NO Type _____ Amount _____
HOLE SEAL
Diam. From To Material From To Amount
14 0 45 BENTONITE 0 10 20 SACKS
12 45 145 CEMENT 10 145 100 SACKS
10 145 245 _____

(11) WATER BEARING ZONES:
Depth at which water was first found 90
From To Est Flow Rate SWL
90 105 50+ GPM 78
165 245 250+ GPM 80

Seal placement method C&SET PLUG&PUSH
Backfill: from _____ ft to _____ ft Material _____
Gravel: from _____ ft to _____ ft Size _____

(12) WELL LOG:
Material Ground elevation
From To SWL
TOP SOIL 0 2
LIGHTLY CEMENTED SAND, GRAVEL & BOULDERS 2 28
LOOSE GRAVEL 28 33
LIGHTLY CEMENTED SAND, GRAVEL & BOULDERS 33 165 78
LIGHTLY CEMENTED SAND & GRAVEL 165 240
LIGHTLY CEMENTED SAND & GRAVEL WITH 240 80
SEAMS OF BLUE CLAY 245
SET 35 FEET OF 14" STARTER PIPE, PULLED
OUT WHILE GROUTING.

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 10 +1 145 .250 STEEL WELDED
Liner 8 0 245 .250 STEEL WELDED

TED PULLIAM WELL DRILLING
9480 S.E. 172nd
Boring, Oregon 97009
Phone 665-3353

Date started 06/19/02 Completed 06/19/02

Final Location of shoe(s) 7 1/2"-245'; 9 1/2"-145'

(7) PERFORATIONS/SCREENS:
[X] Perf. Method AIR KNIFE
[] Screens Type _____ Material _____
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
220 245 1/8X2 4000 _____ LINER

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR
Yield GPM Draw-down Drill stem at Time
250 _____ 240 1 hr.

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David Pulliam* WWC Number 616
Date 6/24/02

Temperature of water 51F Depth Artesian Flow Found _____
Was water analysis done? NO By whom _____
Reason for water not suitable for use _____
Depth of strata _____