

State of Oregon

State Well ID L60650

WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 1

Start Card # 140113

(1) OWNER: Well No. L60650  
 Name JEFF HARDIN  
 Address 31544 SE BLUFF ROAD  
 City GRESHAM St OR Zip 97080

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOMESTIC

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 340 ft  
 Explosives used NO Type Amount

| HOLE  |      |     | SEAL      |      |    |          |
|-------|------|-----|-----------|------|----|----------|
| Diam. | From | To  | Material  | From | To | Amount   |
| 10    | 0    | 54  | BENTONITE | 0    | 54 | 32 SACKS |
| 7 5/8 | 54   | 340 |           |      |    |          |

Seal placement method POURED IN

Backfill: from 50 ft to 54 ft Material BENTONITE  
 Gravel: from \_\_\_ ft to \_\_\_ ft Size \_\_\_\_\_

(6) CASING/LINER:

| Casing | Diam. | From | To   | Gauge | Material | Connection |
|--------|-------|------|------|-------|----------|------------|
| 6      | +1    | 340  | .250 | STEEL | WELDED   |            |

Liner

Final Location of shoe(s) 340' 5 1/2" TUBEX

(7) PERFORATIONS/SCREENS:

☒ Perf. Method AIR KNIFE☐ Screens Type \_\_\_\_\_ Material \_\_\_\_\_

| From | To  | Slot Size | Number | Diam. | Tele/pipe Size | Casing/liner |
|------|-----|-----------|--------|-------|----------------|--------------|
| 325  | 340 | 1/8X2     | 400    |       |                | CASING       |

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

| Yield GPM | Draw-down | Drill stem at | Time  |
|-----------|-----------|---------------|-------|
| 35        |           | 340           | 1 hr. |

Temperature of water 52F Depth Artesian Flow Found \_\_\_\_\_

Was water analysis done? NO By whom \_\_\_\_\_

Reason for water not suitable for use \_\_\_\_\_

Depth of strata \_\_\_\_\_

(9) LOCATION OF WELL by legal description:

County MULT Lat. ° ' " Long. ° ' "  
 Township 1 S Range 4 E WM.  
 Section 20 SE 1/4 SE 1/4  
 Tax Lot 27 Lot Block Subdivision  
 Street Address of Well (or nearest Address)  
 31544 SE BLUFF ROAD GRESHAM, OR 97080

(10) STATIC WATER LEVEL:

194 ft. below land surface. Date 10/02/02  
 Artesian pressure \_\_\_\_\_ lb per square in. Date \_\_\_\_\_

(11) WATER BEARING ZONES:

Depth at which water was first found 265

| From | To  | Est Flow Rate | SWL |
|------|-----|---------------|-----|
| 265  | 340 | 35+ GPM       | 194 |

(12) WELL LOG:

| Material                            | Ground elevation | From | To  | SWL |
|-------------------------------------|------------------|------|-----|-----|
| TOP SOIL                            |                  | 0    | 2   |     |
| BROWN CLAY                          |                  | 2    | 26  |     |
| BROWN CLAY & GRAVEL                 |                  | 26   | 35  |     |
| CEMENTED GRAVEL WITH LARGE BOULDERS |                  | 35   | 191 |     |
| CEMENTED GRAVEL                     |                  | 191  | 265 |     |
| FINE BROWN CEMENTED GRAVEL & SAND   |                  | 265  | 340 | 194 |

**RECEIVED**

OCT 11 2002

**TED PULLIAM WELL DRILLING**

9480 S.E. 172nd

Boring, Oregon 97009

Phone 665-3353

WATER RESOURCES DEPT  
SALEM, OREGON

Date started 09/30/02

Completed 10/02/02

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed \_\_\_\_\_ WWC Number \_\_\_\_\_  
 Date \_\_\_\_\_

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Ted Pulliam* WWC Number 616  
 Date 10/08/02