

State of Oregon

State Well ID L63765

WATER WELL REPORT (as required by ORS 537.765)

Page 1 of 2

Start Card # 155439

(1) OWNER: Well No. L63765
 Name DON STURM
 Address 307 SE EVANS ROAD
 City CORBETT St OR Zip 97019

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: DOM.&EXEPT IRRI

(5) BORE HOLE CONSTRUCTION:

Special Construction Approval NO Depth of Compl. Well 960 ft
 Explosives used NO Type Amount

HOLE			SEAL			
Diam.	From	To	Material	From	To	Amount
10	0	340	CEMENT	8	540	135 SACKS
8	340	540	BENTONITE	0	8	6 SACKS
5 1/2	540	960				

Seal placement method C&SET PLUG&PUSH

Backfill: from ___ ft to ___ ft Material

Gravel: from ___ ft to ___ ft Size

(6) CASING/LINER:

Casing	Diam.	From	To	Gauge	Material	Connection
6	+1	540	.250	STEEL	WELDED	

Liner

Final Location of shoe(s) 540' 5 1/2" TUBEX

(7) PERFORATIONS/SCREENS:

☐ Perf. Method
☐ Screens Type Material

From	To	Slot Size	Number	Diam.	Tele/pipe Size	Casing/liner

(8) WELL TESTS: Minimum testing time is 1 hour

Test type AIR

Yield GPM	Draw-down	Drill stem at	Time
40		960	1 hr.
40		960	3 hr.

Temperature of water 53F Depth Artesian Flow Found

Was water analysis done? NO By whom

Reason for water not suitable for use

Depth of strata

(9) LOCATION OF WELL by legal description:

County MULT Lat. ° ' " Long. ° ' "
 Township 1 S Range 4 E WM.
 Section 3 NE 1/4 NE 1/4
 Tax Lot 90 Lot Block Subdivision
 Street Address of Well (or nearest Address)
 307 SE EVANS ROAD CORBETT, OR 97019

(10) STATIC WATER LEVEL:

560 ft. below land surface. Date 08/14/03
 Artesian pressure ___ lb per square in. Date

(11) WATER BEARING ZONES:

Depth at which water was first found 860		Est Flow Rate	SWL
From	To		
860	960	40+ GPM	560
410	440	20 GPM	300

(12) WELL LOG:

Material	Ground elevation		SWL
	From	To	
BROWN CLAY	0	5	
DECOMPOSED ROCK & GRAVEL	5	18	
MEDIUM GRAY BASALTS	18	43	
SOFT BROWN BASALTS	43	54	
MEDIUM GRAY BASALTS	54	60	
SOFT BROWN BASALTS	60	210	
MEDIUM GRAY BASALTS	210	286	
FINE BROWN CEMENTED GRAVEL WITH SAND	286	320	
FINE BROWN & YELLOW CEMENTED SAND&GRAVEL	320	355	
WHITE CLAY	355	357	
FINE BLACK CEMENTED SAND & GRAVEL	357	380	
BLUE CLAY	380	410	
BLACK CEMENTED SAND & GRAVEL	410	440	300
RED CLAY	440	510	
MEDIUM BLACK BASALTS	510	609	
HARD GRAY BASALTS	609	640	
HARD BLACK BASALTS	640	690	
Date started 08/01/03	Completed	08/14/03	

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
 Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *Red Sturms* WWC Number 616
 Date 08/14/03

