

A.M. JANSSEN WELL DRILLING CO. (INC.)  
21075 S.W. T.V. HWY.  
ALOHA, OR 97006

STATE OF OREGON  
WATER SUPPLY WELL REPORT  
(as required by ORS 537.765)

WELL ID # L 72742  
START CARD # 169087

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER Well Number #2  
Name BATLEY NURSERY INC.  
Address 18616 N.W. REEDER RD.  
City PORTLAND State OR Zip 97231

(2) TYPE OF WORK  
 New Well  Deepening  Alteration (repair/condition)  Abandonment

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  Auger  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 235 ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE			SEAL			
Diameter	From	To	Material	From	To	Sacks or pounds
12 1/4	0	235	Cement	0	195	72 Sacks

How was seal placed: Method  A  B  C  D  E  
 Other

Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from 195 ft. to 235 ft. Size of gravel 1C, 12x16

(6) CASING/LINER: 1/16x1/4

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 8	+2	211	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
8	231	235	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Drive Shoe used  Inside  Outside  None  
Final location of shoe(s)

(7) PERFORATIONS/SCREENS:

Perforations Method \_\_\_\_\_  
 Screens Type Wound Wire Material Stainless

From	To	Slot size	Number	Diameter	Telepipe size	Casing	Liner
211	231	.020		8	Pipe	<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

<input checked="" type="checkbox"/> Pump	<input type="checkbox"/> Bailor	<input checked="" type="checkbox"/> Air	Flowing <input type="checkbox"/> Artesian
Yield gal/min	Drawdown	Drill stem at	Time
75	14		1 hr.
200		40	"

Temperature of water 56°F Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County Multnomah Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 2N N or S Range 1W E or W. WM.  
Section 11 NW 1/4 NW 1/4  
Tax Lot 1400 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) \_\_\_\_\_  
19815 N.W. Gilligan Rd

(10) STATIC WATER LEVEL:  
12 ft. below land surface. Date 9-13-04  
Artesian pressure \_\_\_\_\_ lb. per square inch Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found 211

From	To	Estimated Flow Rate	SWL
211	231	200 gpm	12

(12) WELL LOG:  
Ground Elevation \_\_\_\_\_

Material	From	To	SWL
Topsoil	0	1	
Brn clay	1	15	
Soft gry silty cly	15	33	
Sticky gry clay	33	76	
Fine gry muddy sand w/ clay wood.	76	156	
Fine to med blk sand w/some coarse.	156	203	
Fine to med gravel	203	215	12'
Med fine to med coarse gravel.	215	235	8' 12'

Date started 8-30-04 Completed 9-13-04

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.  
WWC Number \_\_\_\_\_  
Signed \_\_\_\_\_ Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
WWC Number 1266  
Signed [Signature] Date 9/16/04