

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765 & OAR 690-205-0210)

MULT 90847

Well # 7
WELL LABEL # L 93471
START CARD # 113344

Instructions for completing this report are on the last page of this form.

(1) LAND OWNER

Owner Well I.D. _____
First Name _____ Last Name _____
Company City of Gresham
Address 1333 N.W. Eastman Park Way
City Gresham State OR Zip 97030

(2) TYPE OF WORK

☒ New Well ☐ Deepening ☐ Conversion
☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD

☐ Rotary Air ☐ Rotary Mud ☐ Cable ☒ Auger ☐ Cable Mud
☐ Reverse Rotary ☐ Other

(4) PROPOSED USE

☐ Domestic ☐ Irrigation ☐ Community
☐ Industrial/Commercial ☐ Livestock ☒ Dewatering ☐ Injection
☐ Thermal ☐ Other

(5) BORE HOLE CONSTRUCTION

Special Standard: ☒ Yes (attach copy)
Depth of Completed Well 50' ft.

BORE HOLE				SEAL			
Dia	From	To	Material	From	To	Amount	Scks/lbs
5 1/2"	0	10'	Bentonite	0	10'	3/8"	360 sacks
4 1/2"	10	21-6"					
4 1/2"	21-6"	50 FT					

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E

☐ Other Poured in + Tamped

Backfill placed from _____ ft. to _____ ft. Material _____

Filter pack from 10' ft. to 50' ft. Material Gravel Size 3/8"

Explosives used: ☐ Yes Type _____ Amount _____

(6) CASING/LINER

Csng	Linr	Dia	+	From	To	Gauge	Steel	Plastic	Welded	Thrd
X		12"	+	3'	13'	3/8"		X		

Shoe ☐ Inside ☐ Outside ☐ Other Location of shoe(s) _____

Temporary casing ☐ Yes Diameter _____ From _____ To _____

(7) PERFORATIONS/SCREENS

Perforations Method _____
Screens Type 12364 ASTM PW 12 SDR 35 Screen Material PW 12 SDR 35 Screen

Perf	Scrn	Csng	Linr	Screen Dia	From	To	Screen/ slot width	Slot length	# of slots	Tele/ pipe size
X	X	12		12"	10'	50'	0.30	3"	11,320	

(8) WELL TESTS: Minimum testing time is 1 hour

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal/min Drawdown Drill stem/Pump depth Duration (hr)
Pump Test 15 GPM AFTER 1 HR

Temperature 53°F Lab analysis ☐ Yes By NO

Water quality concerns? ☐ Yes (describe below)

From	To	Description	Amount	Units
NO				

(9) LOCATION OF WELL (legal description)

County Multnomah Twp 1 N or S Range 3 E or W W.M.
Sec 17 SW 1/4 of the SW 1/4 Tax Lot 00900-0000
Tax Map Number _____ Lot _____

Lat 45° 29' 24" or _____ DMS or DD
Long 122° 0' 23" or _____ DMS or DD

Street Address of Well (or nearest address) 3363 W Powell Loop
Gresham OR 97030

(10) STATIC WATER LEVEL

	Date	SWL (psi)	+	SWL (ft)
Existing Well/Predeepening				
Completed Well	50'			11'

Flowing Artesian? ☐ Yes Dry Hole? ☐ Yes

WATER BEARING ZONES Depth water was first found 12 FT

SWL Date	From	To	Est Flow	SWL (psi)	+	SWL (ft)
9/12/07	12'	14'	156 PM	11 FT		

(11) WELL LOG

Ground Elevation 628'

Material	From	To
Top soil	0'	3'
CLAY BROWN	3'	9'
Gravel + Clay sandy	9'	12'
Loose Gravel + Sand	12'	14'
CLAY BLUE + GRAY	14'	37'
CLAY + COBBLES BROWN	37'	51'

RECEIVED

RECEIVED

OCT 09 2007

JAN 22 2008

WATER RESOURCES DEPT
SALEM, OREGON

WATER RESOURCES DEPT
SALEM, OREGON

Started 9/12/07 Completed 9/24/07

(unbonded) Water Well Constructor Certification

I certify that the work I performed on the construction, deepening, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

License Number _____ Date _____

Signed _____

(bonded) Water Well Constructor Certification

I accept responsibility for the construction, deepening, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

License Number 755 Date 10/21/07

Signed Brad Brant
Contact Info. (optional)