

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

WELL I.D. # L 23084
START CARD # 163724

(1) OWNER: Well Number _____
Name Wayne Miller
Address 37501 E Knieriem Rd.
City Corbett State OR Zip 97019

(2) TYPE OF WORK
☒ New Well ☐ Deepening ☐ Alteration (repair/recondition) ☐ Abandonment

(3) DRILL METHOD:
☐ Rotary Air ☐ Rotary Mud ☒ Cable ☐ Auger
☐ Other

(4) PROPOSED USE:
☒ Domestic ☐ Community ☐ Industrial ☐ Irrigation
☐ Thermal ☐ Injection ☐ Livestock ☐ Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval ☒ Yes ☐ No Depth of Completed Well 181 ft.
Explosives used ☐ Yes ☒ No Type _____ Amount _____

HOLE SEAL
Diameter From To Material From To Sacks or pounds
10 0 40 BENTONITE 0 40 18 SACKS
6" 40 180

How was seal placed: Method ☐ A ☐ B ☐ C ☐ D ☐ E
☐ Other FOAMED TAMPED

Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from 40 ft. to 180 ft. Size of gravel 3/4

(6) CASING/LINER:
Diameter From To Gauge Steel Plastic Welded Threaded
Casing: 40 12 38 32 ☒ ☐ ☒ ☐
Liner: 4 1/2" 18 119 ☐ ☒ ☐ ☐

Final location of shoe(s) _____

(7) PERFORATIONS/SCREENS:
☒ Perforations Method SAW
☐ Screens Type _____ Material _____
From To Slot size Number Diameter Tele./pipe size Casing Liner
90 180 1/8 510 4 1/2 6" ☐ ☒

(8) WELL TESTS: Minimum testing time is 1 hour

☒ Pump ☒ Bailor ☐ Air ☐ Flowing
Yield gal/min Drawdown Drill stem se Time
10 GPM AFTER 1 HR BAILOR 1 hr
8 GPM AFTER 1 HR PUMP

Temperature of water 53 Depth Artesian Flow Found _____
Was a water analysis done? ☐ Yes By whom _____
Did any strata contain water not suitable for intended use? ☐ Too little
☐ Salty ☐ Muddy ☐ Odor ☐ Colored ☐ Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:

County MULT Latitude _____ Longitude _____
Township 01S N or S Range 04E E or W. WM. _____
Section 13 1/4 1/4
Tax Lot 500 Lot _____ Block _____ Subdivision _____

Street Address of Well (or nearest address) 38775 SE. TRONTLEH
Rd. Corbett OR 97019

(10) STATIC WATER LEVEL:
76 ft. below land surface Date 7/17/07
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:

Depth at which water was first found 165

From	To	Estimated Flow Rate	SWL
<u>165</u>	<u>173</u>	<u>10 GPM</u>	<u>110</u>

(12) WELL LOG:

Ground Elevation 887

Material	From	To	SWL
<u>TOP SOIL</u>	<u>0</u>	<u>2</u>	<u>0</u>
<u>CLAY YELLOW</u>	<u>2</u>	<u>6</u>	<u>0</u>
<u>CLAY RED HARD</u>	<u>6</u>	<u>32</u>	<u>0</u>
<u>ROCK SOFT</u>	<u>32</u>	<u>165</u>	<u>76</u>
<u>ROCK POROUS</u>	<u>165</u>	<u>173</u>	<u>76</u>
<u>ROCK GREY</u>	<u>173</u>	<u>181</u>	<u>76</u>

RECEIVED

JUL 10 2008

WATER RESOURCES DEPT
SALEM, OREGON

Date started 6/13/07 Completed 7/19/07

(unbonded) Water Well Constructor Certification:

I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number _____

Signed _____ Date _____

(bonded) Water Well Constructor Certification:

I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 153

Signed BRAD BRUNT Date 7/19/07

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER

This log received from the landowner.
Received in Salem office July 10, 2008.