

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310
within 30 days from the date
of well completion.

WATER WELL REPORT

STATE OF OREGON

(Please type or print)

(Do not write above this line)

State Well No. 75/3w-7

State Permit No. _____

(1) OWNER:

Name DON MEYER

Address 3795 GADSDEN RD. N.W.
SALEM ORE. 97304

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL:

Rotary ☒ Driven ☐
☐ Jetted ☐
☐ Bored ☐

(4) PROPOSED USE (check):

Domestic ☒ Industrial ☐ Municipal ☐
Irrigation ☐ Test Well ☐ Other ☐

(5) CASING INSTALLED:

6" Diam. from +1 ft. to 22 ft. Gage 1/4
" Diam. from _____ ft. to _____ ft. Gage _____
" Diam. from _____ ft. to _____ ft. Gage _____

(6) PERFORATIONS:

Perforated? ☐ Yes ☒ No.

Type of perforator used _____

Size of perforations _____ in. by _____ in.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.
_____ perforations from _____ ft. to _____ ft.

(7) SCREENS:

Well screen installed? ☐ Yes ☒ No

Manufacturer's Name _____
Type _____ Model No. _____
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.
Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

(8) WELL TESTS:

Drawdown is amount water level is
lowered below static level

AIR
a pump test made? ☒ Yes ☐ No If yes, by whom? SNEED
Yield: 75 gal./min. with 104 ft. drawdown after 1 hrs.

" " " "
" " " "

Boiler test _____ gal./min. with _____ ft. drawdown after _____ hrs.

Artesian flow _____ g.p.m.

Temperature of water 50° Depth artesian flow encountered _____ ft.

(9) CONSTRUCTION:

Well seal—Material used CEMENT
Well sealed from land surface to 22 ft.
Diameter of well bore to bottom of seal 10 in.
Diameter of well bore below seal 6 in.
Number of sacks of cement used in well seal 8 sacks
How was cement grout placed? CEMENT PUMP

Was a drive shoe used? ☐ Yes ☒ No Plugs No Size: location _____ ft.

Did any strata contain unusable water? ☐ Yes ☒ No

Type of water? _____ depth of strata _____

Method of sealing strata off _____

Was well gravel packed? ☐ Yes ☒ No Size of gravel: _____

Gravel placed from _____ ft. to _____ ft.

(10) LOCATION OF WELL:

County Polk Driller's well number _____
1/4 1/4 Section 7 T. 7S R. 3W W.M.

Bearing and distance from section or subdivision corner _____

(11) WATER LEVEL: Completed well.

Depth at which water was first found 215 ft.

Static level 109 ft. below land surface. Date 5-16-80

Artesian pressure _____ lbs. per square inch. Date _____

(12) WELL LOG:

Diameter of well below casing 6"

Depth drilled 225 ft. Depth of completed well 223 ft.

Formation: Describe color, texture, grain size and structure of materials;
and show thickness and nature of each stratum and aquifer penetrated,
with at least one entry for each change of formation. Report each change in
position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOP SOIL	6	1	
CLAY GRAY STICKY	1	2	
CLAY BANG STICKY	2	3	
BASALT WEATH/BAULDERS	3	17	
" DENSE	17	215	
" DECOMPOSED	215	217	
" BAKED CLAY	217	225	109

RECEIVED

JUN 4 1980

WATER RESOURCES DEPT
SALEM, OREGON

Work started 5-12 1980 Completed 5-16 1980

Date well drilling machine moved off of well 5-16 1980

Drilling Machine Operator's Certification:

This well was constructed under my direct supervision.
Materials used and information reported above are true to my
best knowledge and belief.

[Signed] R. Sneed Date 5-29, 1980
(Drilling Machine Operator)

Drilling Machine Operator's License No. 940

Water Well Contractor's Certification:

This well was drilled under my jurisdiction and this report is
true to the best of my knowledge and belief.

Name R. F. SNEED WELL DRILLING
(Person, firm or corporation) (Type or print)

Address 4750 ELIZABETH N. SALEM ORE

[Signed] R. F. Sneed
(Water Well Contractor)

Contractor's License No. 6 Date 6-2, 1980