

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

RECEIVED POLK 3348

AUG 29 1985 PLEASE TYPE or PRINT IN INK

POLK
3348

85/5W-23

(for official use only)

(1) OWNER: WATER RESOURCES DEPT

Name Mr. & Mrs. Louis J. Fourkowski
Address 11190/11190 Bursell Rd.
City Dallas State OR. 97338

(2) TYPE OF WORK (check):

New Well ☒ Deepening ☐ Reconditioning ☐ Abandon ☐

If abandonment, describe material and procedure in Item 12.

(3) TYPE OF WELL: (4) PROPOSED USE (check):

Rotary Air ☐ Driven ☐ Domestic ☒ Industrial ☐ Municipal ☐
Rotary Mud ☐ Dug ☐ Irrigation ☐ Thermal: ☐ Withdrawal ☐ Reinjection ☐
Cable ☒ Bored ☐ Other: ☐ Piezometric ☐ Grounding ☐ Test ☐

(5) CASING INSTALLED: Steel ☒ Plastic ☐

6" Diam. from 0' ft. to 90' ft. Gauge 7"
" Diam. from " ft. to " ft. Gauge "

LINER INSTALLED: Steel ☐ Plastic ☐

" Diam. from " ft. to " ft. Gauge "

(6) PERFORATIONS: Perforated? ☐ Yes ☒ No

Size of perforations in. by in.
perforations from " ft. to " ft.
perforations from " ft. to " ft.
perforations from " ft. to " ft.

(7) SCREENS: Well screen installed? ☐ Yes ☒ No

Manufacturer's Name
Type Model No.
Diam. Slot Size Set from " ft. to " ft.
Diam. Slot Size Set from " ft. to " ft.

(8) WELL TESTS: Drawdown is amount water level is lowered below static level

Was a pump test made? ☐ Yes ☐ No If yes, by whom?
Yield: gal./min. with ft. drawdown after hrs.

Air test gal./min. with drill stem at ft. hrs.

Bailer test 24 gal./min. with 82 ft. drawdown after 2 hrs.

Artesian flow g.p.m.

Temperature of water 52° Depth artesian flow encountered " ft.

(9) CONSTRUCTION: Special standards: Yes ☐ No ☒

Well seal—Material used CEMENT
Well sealed from land surface to 31' ft.

Diameter of well bore to bottom of seal 10" in.

Diameter of well bore below seal 6 in.

Amount of sealing material 9 sacks ☒ pounds ☐

How was cement grout placed? CONDUCTOR PIPE

Was pump installed? YES Type SUB HP 3 Depth 89 ft.

Was a drive shoe used? ☒ Yes ☐ No Plugs NO Size: location " ft.

Did any strata contain unusable water? ☒ Yes ☐ No MUDDY +

Type of Water? IRONY depth of strata 65' to 70'

Method of sealing strata off CASED

Was well gravel packed? ☐ Yes ☒ No Size of gravel: " ft.

Gravel placed from " ft. to " ft.

(10) LOCATION OF WELL by legal description:

County Polk 1/4 of Section 23 of
Township 08 Range 5W WM.
(Township is North or South) (Range is East or West)

Tax Lot Lot Block Subdivision

MAILING ADDRESS OF WELL (or nearest address) 11190 Bursell Rd.
Dallas, Or., 97338

(11) WATER LEVEL of COMPLETED WELL:

Depth at which water was first found 95' to 99' ft.

Static level 18' ft. below land surface. Date 8-24-85

Artesian pressure lbs. per square inch. Date

(12) WELL LOG: Diameter of well below casing 6"

Depth drilled 100' ft. Depth of completed well 100' ft.

Formation: Describe color, texture, grain size and structure of materials; and show thickness and nature of each stratum and aquifer penetrated, with at least one entry for each change of formation. Report each change in position of Static Water Level and indicate principal water-bearing strata.

MATERIAL	From	To	SWL
TOPSOIL	0	2	
CLAY YELLOW COLOR	2	26	
CLAY BLUE STICKY	26	65	
CLAYSTONE GRAY MEALY	65	70	18'
CLAYSTONE WASHY	70	78	
CLAY GRAY STICKY	78	95	
CLAYSTONE GRAY MEALY	95	100	18'

THIS WELL REQUIRED 2 DAYS +
2 NIGHTS OF STEADY PUMPING
TO CLEAR UP A MURKY CONDITION

Date work started 8-14-85 / completed 8-24-85

Date well drilling machine moved off of well 8-28 19 85

(unbonded) Water Well Constructor Certification (if applicable):

This well was constructed under my direct supervision. Materials used and information reported above are true to my best knowledge and belief.

[Signed] Richard F. Sneed Date 8-28, 19 85

(bonded) Water Well Constructor Certification:

Bond 45 86 50 Issued by: UNITED PACIFIC
(number) (Surety Company Name)

On behalf of Richard F. Sneed
(type or print name of Water Well Constructor)

This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief:

(Signed) Richard F. Sneed #6
(Water Well Constructor)

(Dated) 8-28-85

NOTICE TO WATER WELL CONSTRUCTOR

The original and first copy of this report
are to be filed with the

WATER RESOURCES DEPARTMENT,
SALEM, OREGON 97310

within 30 days from the date of well completion.

SP 46866-690