

16.

RECEIVED

8s/4w/28bd
POLK 420 (START CARD) # W-26327

STATE OF OREGON
WATER WELL REPORT
(as required by ORS 537.765)

MAR 23 1992

(1) OWNER: Well Number: _____
Name City of Independence WATER RESOURCES DEPT County Polk Latitude _____ Longitude _____
Address PO Box 7-240 Monmouth, OREGON Township 8-S N or S, Range 4-W E or W, WM.
City Independence State OR Zip _____
Section 28 SE 1/4 NW 1/4

(2) TYPE OF WORK:
 New Well Deepen Recondition Abandon

(3) DRILL METHOD
 Rotary Air Rotary Mud Cable
 Other _____

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Other _____

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 80 ft.
Explosives used Yes No Type _____ Amount _____

HOLE			SEAL			Amount
Diameter	From	To	Material	From	To	sacks or pounds
12"	0	26	Cement	0	26	13 Sacks
8	26	80				

How was seal placed: Method A B C D E
 Other _____
Backfill placed from _____ ft. to _____ ft. Material _____
Gravel placed from _____ ft. to _____ ft. Size of gravel _____

Casing/Liner	Diameter	From	To	Gauge	Type			
					Steel	Plastic	Welded	Threaded
Casing:	8	11.5	79	.250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:					<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 79

(7) PERFORATIONS/SCREENS:
 Perforations Method Mills knife
 Screens Type _____ Material _____

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
55	74	8x1/4	222			<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour
 Pump Bailer Air Flowing Artesian
Yield gal/min 60 Drawdown 1 ft Drill stem at _____ Time 1 hr.

Temperature of water 56 Depth Artesian Flow Found _____
Was a water analysis done? Yes By whom _____
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other _____
Depth of strata: _____

(9) LOCATION OF WELL by legal description:
County Polk Latitude _____ Longitude _____
Township 8-S N or S, Range 4-W E or W, WM.
Section 28 SE 1/4 NW 1/4
Tax Lot _____ Lot _____ Block _____ Subdivision _____
Street Address of Well (or nearest address) In South Well Field behind 6165 Corvallis Rd

(10) STATIC WATER LEVEL:
49 ft. below land surface. Date 2-25-92
Artesian pressure _____ lb. per square inch. Date _____

(11) WATER BEARING ZONES:
Depth at which water was first found 2 ft

From	To	Estimated Flow Rate	SWL
55	76	100T	49

(12) WELL LOG: Ground elevation _____

Material	From	To	SWL
Top Soil	0	2	
Brown Clay	2	12	
Yellow Brown Clay	12	18	
Yellow Pink Clay	18	24	
Brown Silty clay	24	35	
Clay with gravel			
Seams	35	47	
Sand & gravel with brown silt	47	55	
Loose Sand & gravel	55	73	49
Gray clay & gravel	73	76	49
Sandy Blue Clay	76	80	-

Date started 2-18-92 Completed 2-26-92

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon well construction standards. Materials used and information reported above are true to my best knowledge and belief.
Signed Wm E Smith WWC Number 175
Date 2-26-92

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon well construction standards. This report is true to the best of my knowledge and belief.
Signed Floyd G. Spivey WWC Number 1273
Date 2-26-92