

POLK 50030

POLK 50030

FEB 20 1996  
WATER RESOURCES DE  
SALEM, OREGON  
Co S 4 W 12 E AD  
82385  
(START CARD) #

STATE OF OREGON  
WATER SUPPLY WELL REPORT  
(as required by ORS 537.765)

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number 1  
Name Raymond & Patricia Connor  
Address 5651 Zena Rd NW  
City Salem State Ore Zip 97304

(2) TYPE OF WORK  
 New Well  Deepening  Alteration (repair/recondition)  Abandonment

(3) DRILL METHOD:  
 Rotary Air  Rotary Mud  Cable  Auger  
 Other

(4) PROPOSED USE:  
 Domestic  Community  Industrial  Irrigation  
 Thermal  Injection  Livestock  Other

(5) BORE HOLE CONSTRUCTION:  
Special Construction approval  Yes  No Depth of Completed Well 140' ft.  
Explosives used  Yes  No Type \_\_\_\_\_ Amount \_\_\_\_\_

HOLE		SEAL					
Diameter	From To	Material	From To	Sacks or pounds			
10"	0 40'	cement	35' 39'	1 Bag			
8"	40 78'	Bentonite					
6"	79 140'		55' 0'	16 Bags			

How was seal placed: Method  A  B  C  D  E  
 Other milled to top with dry bentonite  
Backfill placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Material \_\_\_\_\_  
Gravel placed from \_\_\_\_\_ ft. to \_\_\_\_\_ ft. Size of gravel \_\_\_\_\_

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	1'	79'	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner: 4"	3'	140'	160	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) \_\_\_\_\_

(7) PERFORATIONS/SCREENS:

Perforations Method saw cut  
 Screens Type \_\_\_\_\_ Material \_\_\_\_\_

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
85'	140'	1/8"	65	6" round		<input type="checkbox"/>	<input checked="" type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump  Bailor  Air  Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
30 gpm		120'	1 hr.

Temperature of water 55° Depth Artesian Flow Found \_\_\_\_\_  
Was a water analysis done?  Yes By whom \_\_\_\_\_  
Did any strata contain water not suitable for intended use?  Too little  
 Salty  Muddy  Odor  Colored  Other \_\_\_\_\_  
Depth of strata: \_\_\_\_\_

(9) LOCATION OF WELL by legal description:  
County: polk Latitude \_\_\_\_\_ Longitude \_\_\_\_\_  
Township 6 S N or S Range 4 W E or W. WM.  
Section 26 se 1/4 ne 1/4  
Tax Lot 104 Lot \_\_\_\_\_ Block \_\_\_\_\_ Subdivision \_\_\_\_\_  
Street Address of Well (or nearest address) 5651 Zena Rd  
Salem or 97304

(10) STATIC WATER LEVEL:  
63' ft. below land surface. Date 2/16/96  
Artesian pressure \_\_\_\_\_ lb. per square inch. Date \_\_\_\_\_

(11) WATER BEARING ZONES:  
Depth at which water was first found \_\_\_\_\_

From	To	Estimated Flow Rate	SWL
<del>83'</del> 83'	120'	30 gpm	

(12) WELL LOG:  
Ground Elevation \_\_\_\_\_

Material	From	To	SWL
soil	0	1	
brown clay	1	10	
Brown clay w/ weathered rock	10	50	
partly weathered rock	50	83	
gray sandstone	83	138	
Brown claystone	138	140	

**ROBINSON DRILLING  
WELLS & PUMPS  
4520 Dallas-Salem Hwy.  
Salem, Ore. 97304  
371-1844**

Date started 2/8/96 Completed 2/16/96

(unbonded) Water Well Constructor Certification:  
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.  
WWC Number \_\_\_\_\_  
Signed \_\_\_\_\_ Date \_\_\_\_\_

(bonded) Water Well Constructor Certification:  
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.  
WWC Number 1585  
Signed [Signature] Date 2-20-96



Oregon Water Resources Department
725 Summer Street NE, Suite A
Salem Oregon 97301
(503) 986-0900
www.wrd.state.or.us

Application for
Well ID Number

RECEIVED

OCT 02 2017

OWRD

Do not complete if the well already has a Well Identification Number.

I. OWNER INFORMATION

Current Owner Name (please print): ZENITH VINEYARD LLC
Mailing Address: 5652 ZENA RD NW
City, State, Zip: SALM OR 97304
Mail Well ID Tag to: [X] SAME AS ABOVE [ ] In Care Of (C/O)
Name & Address: (in person)
City, State, Zip:

II. WELL LOCATION INFORMATION (Please fill out as completely as possible)

Township: 6 (North / South) Range: 4 (East / West) Section: 28 55 1/4 of the NE 1/4
Tax Lot (usually last 3-5 numbers of Tax Map #): 104 County POLK
GPS Coordinates:
Street Address of Well, City: 5651 ZENA RD NW SALM
If the property had a different street address in the past:

III. GENERAL WELL INFORMATION (Please fill out as completely as possible, AND attach copy of Well Log, if available)

Use of Well (domestic, irrigation, commercial, industrial, monitoring): DOMESTIC, IRRIGATION
Date Well Constructed (or property built): 02/08/96 Total Well Depth: 140 Casing Diameter: 6"
Owner at time the well was constructed (if known): PAT O'CONNOR Well Log # (if known): POLK 50030
Other Information:

SUBMITTED BY (please print): TIMOTHY S RAMEY
PHONE: 503-991-1115 EMAIL &/or FAX: Tim@ZENITHVINEYARD.COM

Send application to: Oregon Water Resources Department 725 Summer St NE, Suite A, Salem, Oregon 97301; or fax to (503) 986-0902.
Applications are processed in the order they are received, and Well ID Numbers are mailed within 4-5 business days.

For Official Use Only by the Oregon Water Resources Department:

Received Date:

10-2-17

Well Log Number:

POLK 50030

Well Identification #:

L-127841