

RECEIVED

State of Oregon
WATER WELL REPORT (as required by ORS 537.765)

State Well ID L36777
Start Card # 133821

OCT 11 2000

WATER RESOURCES DEPT.
SALEM, OREGON

(1) OWNER: Well No. 2010
Name BILL HOLLORAN
Address 2636 SW SCHAEFFER RD
City WEST LINN St OR Zip 97068

(9) LOCATION OF WELL by legal description:
County POLK Lat. ' ' ' ' Long. ' ' ' '
Township 7 S Range 4 W WM.
Section 4 NE 1/4 NW 1/4
Tax Lot 800 Lot Block Subdivision
Street Address of Well (or nearest Address)
4195 OAK GROVE RD RICKREAL, OR

(2) TYPE OF WORK: NEW WELL

(3) DRILL METHOD: ROTARY AIR

(4) PROPOSED USE: IRRIGATION

(10) STATIC WATER LEVEL:
22 ft. below land surface. Date 10/06/00
Artesian pressure ___ lb per square in. Date ___

(5) BORE HOLE CONSTRUCTION:
Special Construction Approval NO Depth of Compl. Well 274 ft
Explosives used NO Type Amount
HOLE SEAL
Diam. From To Material From To Amount
10 0 61 BENTONITE CHIP 0 50 24 SAX
6 78 274 ANNULAR BACFIL
W/BENTNITE CHI 50 61 4 SAX

(11) WATER BEARING ZONES:
Depth at which water was first found 121
From To Est Flow Rate SWL
121 131 4 22
131 182 1 22
182 232 1 22

Seal placement method POURED/PROBED
Backfill: from ___ ft to ___ ft Material
Gravel: from ___ ft to ___ ft Size

(12) WELL LOG:
Ground elevation 475
Material From To SWL
TOP SOIL 0 3
CLAY, RED 3 11
CLAY, TAN 11 41
SANDSTONE, RED 41 121
SANDSTONE, RED W/OCC HARD TAN SANDSTONE 121 131 22
SANDSTONE, RED 131 182 22
SANDSTONE, RED W/OCC TAN LAYERS 182 232 22
SANDSTONE, RED W/OCC GRAY CLAYSTONE 232 263
CLAYSTONE, GRAY W/RED STREAKS 263 274

(6) CASING/LINER:
Diam. From To Gauge Material Connection
Casing 6 +2 78 .25 STEEL WELDED

Liner 4 0 274 SDR26 PLASTIC WELDED

Final Location of shoe(s) 78

DAVE PAYSINGER, BLUE WATER DRILLING CO.
(503) 868-7878

(7) PERFORATIONS/SCREENS:
[X] Perf. Method ELECTRIC SAW
[_] Screens Type Material
Slot Tele/pipe
From To Size Number Diam. Size Casing/liner
94 134 .1X2" 3 LINER
154 174 .1X7" 36 LINER
194 234 .1X2" 3 LINER
254 274 .1X7" 36 LINER

Date started 10/05/00 Completed 10/06/00

(8) WELL TESTS: Minimum testing time is 1 hour
Test type AIR

Yield GPM Draw-down Drill stem at Time
6 ___ 274 1 hr.
6 ___ 254 2

(unbonded) Water Well Constructor Certification: I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to my best knowledge and belief.

Signed _____ WWC Number _____
Date _____

(bonded) Water Well Constructor Certification: I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

Signed *David L. Paysinger* WWC Number 1438
Date 10/06/00