

STATE OF OREGON
WATER SUPPLY WELL REPORT
(as required by ORS 537.765)

(WELL I.D.)# L 65554
(START CARD) # 166050

Instructions for completing this report are on the last page of this form.

(1) OWNER: Well Number 1
Name Don & Sharon Roberts - Clay & Rhonda Johnson
Address 3395 Pacific Hwy
City Independence, State OR Zip 97351

(2) TYPE OF WORK
 New Well Deepening Alteration (repair/recondition) Abandonment

(3) DRILL METHOD:
 Rotary Air Rotary Mud Cable Auger
 Other

(4) PROPOSED USE:
 Domestic Community Industrial Irrigation
 Thermal Injection Livestock Other

(5) BORE HOLE CONSTRUCTION:
Special Construction approval Yes No Depth of Completed Well 260 ft.
Explosives used Yes No Type Amount

HOLE SEAL

Diameter	From	To	Material	From	To	Sacks or pounds
10"	0	18	Bentonite	0	18	9 bags
6"	18	260				

How was seal placed: Method A B C D E
 Other Filled to top with dry bentonite
Backfill placed from ft. to ft. Material
Gravel placed from ft. to ft. Size of gravel

(6) CASING/LINER:

Diameter	From	To	Gauge	Steel	Plastic	Welded	Threaded
Casing: 6"	+1	61	250	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Liner:				<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Final location of shoe(s) 61'

(7) PERFORATIONS/SCREENS:

Perforations Method down hole perforator
 Screens Type Material

From	To	Slot size	Number	Diameter	Tele/pipe size	Casing	Liner
22	30	.250	120	1" long	6"	<input checked="" type="checkbox"/>	<input type="checkbox"/>
40	50	.250	120	1" long	6"	<input checked="" type="checkbox"/>	<input type="checkbox"/>

(8) WELL TESTS: Minimum testing time is 1 hour

Pump Bailer Air Flowing Artesian

Yield gal/min	Drawdown	Drill stem at	Time
20		60'	1 hr.

Temperature of water 53° Depth Artesian Flow Found
Was a water analysis done? Yes By whom
Did any strata contain water not suitable for intended use? Too little
 Salty Muddy Odor Colored Other
Depth of strata:

(9) LOCATION OF WELL by legal description:
County Polk Latitude Longitude
Township 8 S Range 4 W WM.
Section 18 NE 1/4 SW 1/4
Tax Lot 202 Lot Block Subdivision
Street Address of Well (or nearest address) Same

(10) STATIC WATER LEVEL:
12' ft. below land surface. Date 8/12/2004
Artesian pressure lb. per square inch. Date

(11) WATER BEARING ZONES:
Depth at which water was first found 22'

From	To	Estimated Flow Rate	SWL
22	33	3 GPM	12
40	50	7 GPM	12
63	71	10 GPM	

(12) WELL LOG:
Ground Elevation

Material	From	To	SWL
Brown clay - gray blue clay sandy	0	3	
Gravels - sandy gray blue clay - small	3	22	12
Gravels - sandy blue clay small	22	33	
Gray blue clay black sand	33	52	
Gray blue clay sandy	52	63	
Sand blue black pea gravel	63	71	
Gray brown clay firm	71	260	

Ron Robinson Well Drilling
4520 Salem Dallas Hwy NW
Salem, OR 97304
503.371.1844

RECEIVED
AUG 23 2004
WATER RESOURCES DEPT
SALEM, OREGON

Date started 8/9/2004 Completed 8/12/2004

(unbonded) Water Well Constructor Certification:
I certify that the work I performed on the construction, alteration, or abandonment of this well is in compliance with Oregon water supply well construction standards. Materials used and information reported above are true to the best of my knowledge and belief.

WWC Number
Signed Date

(bonded) Water Well Constructor Certification:
I accept responsibility for the construction, alteration, or abandonment work performed on this well during the construction dates reported above. All work performed during this time is in compliance with Oregon water supply well construction standards. This report is true to the best of my knowledge and belief.

WWC Number 1585
Signed Date 8/13/2004

ORIGINAL & FIRST COPY-WATER RESOURCES DEPARTMENT SECOND COPY-CONSTRUCTOR THIRD COPY-CUSTOMER

RECEIVED
OVER THE COUNTER